



REPUBLIKA E SHQIPERISE

BASHKIA KAMEZ

PREVENTIV

OBJEKTI : Ndertim Rruget Agim NIVICA + Seg . Adem JASHARI + Dy Rrugica pingul me Abdyl Elmazi +Rruga Gani Duraku + Ndriçimi I rruges Hysen Cino + Rruga Ali IBRA , PASKUQAN 2 VRESHTE , Njesia Administrative Paskuqan , Bashkia Kamez

OBJEKTI : Ndertim Rruga " Rruget Pingul me Abdyl elmazi " Paskuqan 2 , Bashkia Kamez

Gjatesia L= 230 m , B=6m , basfalt = 4.5m+1x0.5m + 1x1 m

L= 230

A	An.	Emertimi i Punimeve	Njesia	Sasia	Cmimi	Vlera
I	PUNIME NE RRUGE					
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA		
1	3.139	Germim dheu me eskavator	m ³	207		
2	3.158/5a	Transport dheu me auto 5km	m ³	207		
3	An. 8	Mbushje me çakell shkembor	m ³	103.5		
4	3.211	Shtrese çakelli T=20cm	m ²	1035		
5	3.212/b	Shtrese stabilizanti t=10cm	m ²	1035		
6	3.222/2	Shtrese binderi 1x6 cm	m ²	1035		
7	3.226/1	Shtrese asfaltbetoni 1x4cm	m ²	1035		
8	2/111/2	Mure betoni C12/15(themel,xokol betoni)	m ³	86.25		
9	3.288	F.V Hekur betoni I zakonshem O > 10 mm	ton	2.16		
10	An.	Ngritje pusete+kapak gize+pastrim me makineri	cope	4		
11	An.	Spostim shtyllash	cope	5.75		
12	2/426/2	Prishje mure me blloqe + transport	m ³	138		
13	An.152	Vizime me boje bikomponente 15cm	ml	690		
14	An.96	Tabele sinjalistike 60-90cm	cope	4		
		SHUMA I				
II	PUNIME NE KUB					
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA		
1	3.139	Germim dheu me eskavator	m ³	92		
2	3.158/5a	Transport çakelli me auto 5km	m ³	92		
3	3 An. 8	Mbushje me çakell shkembor	m ³	46		
4	3.an/1t	F.V. Tuba i brinjezuar Ø 315	ml	230		
5	2.262/4	Shtrese betoni c 16/20Kunete betoni M - 200	m ³	11.5		
6	2.An.23	Puseta shiu me zgare 40x60 + kapak gize	cope	6.57		
		SHUMA II				
II	PUNIME NE KUN					
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA		
1	3.139	Germim dheu me eskavator	m ³	59.616		
2	3.158/5a	Transport çakelli me auto 5km	m ³	59.616		
3	3 An. 8	Mbushje me çakell shkembor	m ³	83		
4	3.an/1t	F.V. Tuba I brinjezuar Ø 315	ml	230		
5	An - 20	Pusete shkarkimi b/a, 80 x 80 cm, h = 150 cm	cope	5.0		
		SHUMA II				
III	PUNIME TROTUARE(1x1 m)					
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA		
1	3.139	Germim dheu me eskavator	m ³	70.5		
2	3.158/5a	Transport dheu me auto 5km	m ³	70.5		
3	3 An. 8	Mbushje me çakell shkembor	m ³	35.25		
4	3.208	Shtrese çakelli T=10cm	m ²	188		
5	3.212/a	Shtrese stabilizanti ne trotuar T=5 cm	m ²	188		
6	3.617	F.V. Bordura betoni e parapregatitur M-250 15x25 cm	ml	460		
7	2/262/4	Beton per fiksime bordure C16/20	m ³	13.8		
8	2.109/2	Shtrese betoni trotuari	m ³	18.8		
		SHUMA III				
IV	PUNIME PER NDRICIMIN					
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA		
####	3.654/1	F.V. Tub korrogato Ø80 per elektrikun, ndriçimin	ml	230		

###:	3An/55	F.v puseta elektrike kontrolli PVC 40x40 x40	cope	7	
			SHUMA IV		
			SHUMA A		

OBJEKTI : Ndertim Rruga "Rruga Agim NIVICA " Paskuqan 2 , Bashkia Kamez

Gjatesia L= 650m , B=7m , basfalt = 4.5m+1x0.5m + 2x1 m

L= 650

B	An.	Emertimi i Punimeve	Njesia	Sasia	Cmimi	Vlera
---	-----	---------------------	--------	-------	-------	-------

I PUNIME NE RRUGE

NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA		
1	3.139	Germim dheu me eskavator	m ³	585		
2	3.158/5a	Transport dheu me auto 5km	m ³	585		
3	An. 8	Mbushje me çakell shkembor	m ³	292.5		
4	3.211	Shtrese çakelli T=20cm	m ²	2925		
5	3.212/b	Shtrese stabilizanti t=10cm	m ²	2925		
6	3.222/2	Shtrese binderi 1x6 cm	m ²	2925		
7	3.226/1	Shtrese asfaltbetoni 1x4cm	m ²	2925		
8	2/111/2	Mure betoni C12/15(themel,xokol betoni)	m ³	243.75		
9	3.288	F.V Hekur betoni I zakonshem O > 10 mm	ton	10.97		
10	An.	Ngritje pusete+kapak gize+pastrim me makineri	cope	5		
11	An.	Spostim shtyllash	cope	16.25		
12	2/426/2	Prishje mure me blloqe + transport	m ³	390		
13	An.152	Vizime me boje bikomponente 15cm	ml	1625		
14	An.96	Tabele sinjalistike 60-90cm	cope	4		

SHUMA I

II PUNIME NE KUB

NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA		
1	3.139	Germim dheu me eskavator	m ³	260		
2	3.158/5a	Transport çakelli me auto 5km	m ³	260		
3	3 An. 8	Mbushje me çakell shkembor	m ³	130		
4	3.an/1t	F.V. Tuba I brinjezuar Ø 315	ml	650		
5	2.262/4	Shtrese betoni c 16/20Kunete betoni M - 200	m ³	32.5		
6	2.An.23	Puseta shiu me zgare 40x60 + kapak gize	cope	22.00		

SHUMA II

II PUNIME NE KUN

NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA		
1	3.139	Germim dheu me eskavator	m ³	260		
2	3.158/5a	Transport çakelli me auto 5km	m ³	260		
3	3 An. 8	Mbushje me çakell shkembor	m ³	130		
4	3.an/1t	F.V. Tuba I brinjezuar Ø 315	ml	650		
5	An - 20	Pusete shkarkimi b/a, 80 x 80 cm, h = 150 cm	cope	9.00		

SHUMA II

III PUNIME TROTUARE(2x1 m)

NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA		
1	3.139	Germim dheu me eskavator	m ³	138		
2	3.158/5a	Transport dheu me auto 5km	m ³	138		
3	3 An. 8	Mbushje me çakell shkembor	m ³	69		
4	3.208	Shtrese çakelli T=10cm	m ²	598		
5	3.212/a	Shtrese stabilizanti ne trotuar T= 5 cm	m ²	598		
6	3.617	F.V. Bordura betoni e parapregatitur M-250 15x25 cm	ml	1300		
7	2/262/4	Beton per fiksime bordure C16/20	m ³	39		
8	2.109/2	Shtrese betoni trotuari	m ³	59.8		

SHUMA III

6. PUNIME VEPRA ARTI (MURE MBAJTESE)

1	3.105/a	Germim dheu me eskavator zinxhir 0.5 m ³ , ne kanale gjeresi deri 2 m, prani uji ~1m, kategoria IV, me shk ne mjet	m ³	130		
2	3.158/5a	Transport dheu me auto deri 5.0 km	m ³	130		
3	3.243	Struktura monolite betoni C 16/20 per muret rrethuese	m ³	163		
4	3.287	F V hekur betoni i zakonshem Ø 6 ~ 10mm	ton	1.63		
5	3.288	F V hekur betoni i zakonshem Ø > 12mm	ton	4.1		

SHUMA 6

IV PUNIME PER NDRICIMIN

NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA		
1	3.654/1	F.V. Tub korrogato Ø80 per telefonine	ml	650		

2	3.654/1	F.V. Tub korrogato Ø80 per elektrikun, ndriçimin	ml	650		
3	3An/55	F.v puseta elektrike kontrolli PVC 40x40 x40	cope	12		
			SHUMA IV			
			SHUMA B			

OBJEKTI : Ndertim Rruga "Rruga Gani DURAKU " Paskuqan 2 , Bashkia Kamez

l=180 ml B=4 m bast=3.5m + 1x0.5 m kunete

L= 180

C	An.	Emertimi i Punimeve	Njesia	Sasia	Cmimi	Vlera
I PUNIME NE RRUGE						

NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA		
1	3.139	Germim dheu me eskavator	m ³	162		
2	3.158/5a	Transport dheu me auto 5km	m ³	162		
3	An. 8	Mbushje me çakell shkembor	m ³	63		
4	3.211	Shtrese çakelli T=20cm	m ²	630		
5	3.212/b	Shtrese stabilizanti t=10cm	m ²	630		
6	3.222/2	Shtrese binderi 1x6 cm	m ²	630		
7	3.226/1	Shtrese asfaltbetoni 1x4cm	m ²	630		
8	2/111/2	Mure betoni C12/15(themel,xokol betoni)	m ³	67.50		
9	3.288	F.V Hekur betoni I zakonshem O > 10 mm	ton	1.69		
10	An.	Ngritje pusete+kapak gize+pastrim me makineri	cope	3		
11	An.	Spostim shtyllash	cope	4.00		
12	2/426/2	Prishje mure me blloqe + transport	m ³	108		
13	An.152	Vizime me boje bikomponente 15cm	ml	360		
14	An.96	Tabele sinjalistike 60-90cm	cope	4		

SHUMA I

II PUNIME NE KUB						
-------------------------	--	--	--	--	--	--

NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA		
1	3.139	Germim dheu me eskavator	m ³	72		
2	3.158/5a	Transport çakelli me auto 5km	m ³	72		
3	3 An. 8	Mbushje me çakell shkembor	m ³	36		
4	3.an/1t	F.V. Tuba I brinjezuar Ø 315	ml	180		
5	2.262/4	Shtrese betoni c 16/20Kunete betoni M - 200	m ³	9		
6	2.An.23	Puseta shiu me zgare 40x60 + kapak gize	cope	5.14		

SHUMA II

II PUNIME NE KUN						
-------------------------	--	--	--	--	--	--

NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA		
1	3.139	Germim dheu me eskavator	m ³	72		
2	3.158/5a	Transport çakelli me auto 5km	m ³	72		
3	3 An. 8	Mbushje me çakell shkembor	m ³	36		
4	3.an/1t	F.V. Tuba I brinjezuar Ø 315	ml	180		
5	An - 20	Pusete shkarkimi b/a, 80 x 80 cm, h = 150 cm	cope	4.00		

SHUMA II

SHUMA C

OBJEKTI : Ndertim Rruga " Adem JASHARI " Paskuqan 2 , , Bashkia Kamez

l=225 ml B= 6 m bast=4.5m + 1x0.5 m kunete +1x1 trotuare

L= 250

D	An.	Emertimi i Punimeve	Njesia	Sasia	Cmimi	Vlera
I PUNIME NE RRUGE						

NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA		
1	3.139	Germim dheu me eskavator	m ³	225		
2	3.158/5a	Transport dheu me auto 5km	m ³	225		
3	An. 8	Mbushje me çakell shkembor	m ³	112.5		
4	3.211	Shtrese çakelli T=20cm	m ²	1125		
5	3.212/b	Shtrese stabilizanti t=10cm	m ²	1125		
6	3.222/2	Shtrese binderi 1x6 cm	m ²	1125		
7	3.226/1	Shtrese asfaltbetoni 1x4cm	m ²	1125		
8	2/111/2	Mure betoni C12/15(themel,xokol betoni)	m ³	93.75		
9	3.288	F.V Hekur betoni I zakonshem O > 10 mm	ton	2.34		
10	An.	Ngritje pusete+kapak gize+pastrim me makineri	cope	2		
11	An.	Spostim shtyllash	cope	6.25		
12	2/426/2	Prishje mure me blloqe + transport	m ³	150		
13	An.152	Vizime me boje bikomponente 15cm	ml	750		
14	An.96	Tabele sinjalistike 60-90cm	cope	4		

SHUMA I

II		PUNIME NE KUB		
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA
1	3.139	Germim dheu me eskavator	m ³	100
2	3.158/5a	Transport çakelli me auto 5km	m ³	100
3	3 An. 8	Mbushje me çakell shkembor	m ³	50
4	3.an/1t	F.V. Tuba I brinjezuar Ø 315	ml	250
5	2.262/4	Shtrese betoni c 16/20Kunete betoni M - 200	m ³	12.5
6	2.An.23	Puseta shiu me zgare 40x60 + kapak gize	cope	7.14
SHUMA II				

III		PUNIME TROTUARE(1x1 m)		
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA
1	3.139	Germim dheu me eskavator	m ³	21.25
2	3.158/5a	Transport dheu me auto 5km	m ³	21.25
3	3 An. 8	Mbushje me çakell shkembor	m ³	31.88
4	3.208	Shtrese çakelli T=10cm	m ²	212.50
5	3.212/b	Shtrese stabilizanti ne trotuar T=10cm	m ²	212.50
6	3.617	F.V. Bordura betoni e parapregatitur M-250 15x25 cm	ml	500
7	2/262/4	Beton per fiksime bordure C16/20	m ³	15
8	2.109/2	Shtrese betoni trotuari	m ³	21.25
SHUMA III				

6. PUNIME VEPRRA ARTI (MURE MBAJTESE)

1	3.105/a	Germim dheu me ekskavator zinxhir 0.5 m ³ , ne kanale gjeresi deri 2 m, prani uji ~1m, kategoria IV, me shk ne mjet	m ³	12
2	3.158/5a	Transport dheu me auto deri 5.0 km	m ³	12
3	3.243	Struktura monolite betoni C 16/20 per muret rrethuese	m ³	20
4	3.287	F V hekur betoni i zakonshem Ø 6 ~ 10mm	ton	0.08
5	3.288	F V hekur betoni i zakonshem Ø > 12mm	ton	0.1
SHUMA 6				

IV		PUNIME PER NDRICIMIN		
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA
1	3.654/1	F.V. Tub korrogato Ø80 per telefonine	ml	250
2	3.654/1	F.V. Tub korrogato Ø80 per elektrikun, ndriçimin	ml	250
3	3An/55	F.v puseta elektrike kontrolli PVC 40x40 x40	cope	5
SHUMA IV				
SHUMA D				

OBJEKTI : Ndricimi i Rrugës " Hysen Cino " Paskuqan 1 , , Bashkia Kamez

L= 180

E	An.	Emertimi i Punimeve	Njesia	Sasia
1	3.654/1	F.V. Tub korrogato Ø80 per telefonine	ml	180
2	3.654/1	F.V. Tub korrogato Ø80 per elektrikun, ndriçimin	ml	180
3	3.an/1sh	F.V. Shtylla metalike konike ndriçimi H-9m PAICC-3	cope	5
4	3.an/ksh	F.V. Krah shtylla metalike KRH-MSI 1500/1500/10	cope	5
5	An	F.V Ndricues Led 94W	cope	5
6	An	F.V. morsete tre fazore +siguresa+kapak per shtyllen	cope	5
7	An	F.V Elektroda tokezim komplet l=150m	cope	5
8	4.131/3.6	F.V Kabell Cu me me fuqi -1000V me izolim gome (4x16mmk)	ml	180
9	An	F.V kabell tokezimi 1x3.5mmk	ml	8
10	An	F.V kontaktor 3fazor aktiv me 4pole bobine 220V 40A	cope	1
11	3An/55	F.v puseta elektrike kontrolli PVC 40x40 x40	cope	5
12	An-19	F.v puseta betoni me kapak gize 80x80x100mm	cope	1
13	An.	F.V kuader komandimi per ndriçim rrugor	cope	1
14	An.	F.V kasete shperndarese	cope	1
15	3.139	Germime dheu me ekskavator me goma	m ³	36
16	3.158/5a	Transport dheu me auto 5km	m ³	36
17	2.261	Mbushje me rere	m ³	14.4
18	Man 3 An. 8	Mbushje me cakull shkembor (kanal)	m ³	21.6
SHUMA E				

OBJEKTI : Ndertim Rruga " Ali IBRA " Paskuqan 2 , , Bashkia Kamez

l=325 ml B= 6 m bast=4.5m + 1x0.5 m kunete +1x1 trotuare

L= 325

F	An.	Emertimi i Punimeve	Njesia	Sasia	Cmimi	Vlera
I PUNIME NE RRUGE						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA		

1	3.139	Germim dheu me eskavator	m ³	292.5	
2	3.158/5a	Transport dheu me auto 5km	m ³	292.5	
3	An. 8	Mbushje me çakell shkembor	m ³	148.6	
4	3.211	Shtrese çakelli T=20cm	m ²	1486	
5	3.212/b	Shtrese stabilizanti t=10cm	m ²	1486	
6	3.222/2	Shtrese binderi 1x6 cm	m ²	1486	
7	3.226/1	Shtrese asfaltbetoni 1x4cm	m ²	1486	
8	2/111/2	Mure betoni C12/15(themel,xokol betoni)	m ³	162.50	
9	3.288	F.V Hekur betoni I zakonshem O > 10 mm	ton	5.20	
10	An.	Ngritje pusete+kapak gize+pastrim me makineri	cope	4	
11	An.	Spostim shtyllash	cope	8.13	
12	2/426/2	Prishje mure me blloqe + transport	m ³	195	
13	An.152	Vizime me boje bikomponente 15cm	ml	975	
14	An.96	Tabele sinjalistike 60-90cm	cope	4	
			SHUMA I		
II PUNIME NE KUB					
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	
1	3.139	Germim dheu me eskavator	m ³	130	
2	3.158/5a	Transport çakelli me auto 5km	m ³	130	
3	3 An. 8	Mbushje me çakell shkembor	m ³	65	
4	3.an/1t	F.V. Tuba I brinjzuar Ø 315	ml	325	
5	2.262/4	Shtrese betoni c 16/20Kunete betoni M - 200	m ³	16.25	
6	2.An.23	Puseta shiu me zgare 40x60 + kapak gize	cope	9.29	
			SHUMA II		
III PUNIME TROTUARE(1x0.85 m)					
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	
1	3.139	Germim dheu me eskavator	m ³	30.00	
2	3.158/5a	Transport dheu me auto 5km	m ³	30.00	
3	3 An. 8	Mbushje me çakell shkembor	m ³	41.40	
4	3.208	Shtrese çakelli T=10cm	m ²	276.00	
5	3.212/b	Shtrese stabilizanti ne trotuar T=10cm	m ²	276.00	
6	3.617	F.V. Bordura betoni e parapregatitur M-250 15x25 cm	ml	650	
7	2/262/4	Beton per fiksime bordure C16/20	m ³	19.5	
8	2.109/2	Shtrese betoni trotuari	m ³	27.6	
			SHUMA III		
6. PUNIME VEPRRA ARTI (MURE MBAJTESE)					
1	3.105/a	Germim dheu me eskavator zinxhir 0.5 m ³ , ne kanale gjeresi deri 2 m, prani uji ~1m, kategoria IV, me shk ne mjet	m ³	15	
2	3.158/5a	Transport dheu me auto deri 5.0 km	m ³	15	
3	3.243	Struktura monolite betoni C 16/20 per muret rrethuese	m ³	31.08	
4	3.287	F V hekur betoni i zakonshem Ø 6 ~ 10mm	ton	0.15	
5	3.288	F V hekur betoni i zakonshem Ø > 12mm	ton	0.2	
			SHUMA 6		
IV PUNIME PER NDRICIMIN					
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	
1	3.654/1	F.V. Tub korrogato Ø80 per telefonine	ml	325	
2	3An/55	F.v puseta elektrike kontrolli PVC 40x40 x40	cope	5	
			SHUMA IV		
			SHUMA F		
			Shuma totale e Rrugeve		
			TVSH 20 %		
			TVSH TOTALE		

Preventivues:

Ing. Hajredin MURGU



Drejtori i Pergjithshem

Z.Elvis Gjika



Drejtori P.I-se

Ing. Flora MUÇA

MIRATOI

Rakip SULTI

KRYETAR

