

PREVENTIV PUNIMESH

OBJEKTI: F "Rikonstruksion i rruges Terpan - Teman , Njesia Administrative Terpan L=519"

POROSITËSI: BASHKIA POLICAN

NR.	AN.	ZERAT E PUNIMEVE	NJËSIA	SASIA
		I - Punime dheu		
1	3.2	Prerje bime te vogla Ø10cm	m ²	5,000.00
2	3.5	Preje e sistemim pemesh Ø 41- 75 cm	cope	100.00
3	3.121/b	Germim shkemb i coptuar me ekskavator 0.5 m ³ , shkemb, prani uji ~2m, themele gjeresi >2 m, me shkarkim ne toke	m ³	798.00
4	2.48/an	Germim dheu me ekskavator zingjir, 0.25 m ³ , ne kanale gjeresi > 2 m, toke zak, kategoria III, me shk ne toke	m ³	5,000.00
5	3.124/1a	Germim shkemb mesatar me çekiç me ekskavator me zinxhir	m ³	6,500.00
6	3.189/b	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi > 2 m, toke zak, kategoria III, me shk ne mjet	m ³	7,800.00
7	3.158/1a	Transport me auto deri 1.0 km	m ³	1,500.00
8	3.158/2a	Transport me auto deri 2.0 km	m ³	2,500.00
9	3.158/5a	Transport me auto deri 5.0 km	m ³	3,800.00
Shuma I				
		II - Shtresat rrugore		
1	3.211	Shtrese çakelli mbeturine kave t= 20 cm, perhapur e ngjeshur makineri	m ²	25,965.00
2	3.208	Shtrese çakelli t=10cm, Makadam perhapur e ngjeshur me makineri	m ²	25,965.00
3	3.212/b	Shtrese stabilizant t=10cm	m ²	25,965.00
Shuma II				
		III- Punime Vepra Arti		
		A - Mure mbajtese dhe pritesa + rruge me beton L= 200 ml		
1	3.68/1a	Germim themel (gropa) sip10-30m ² , shkemb bute,h deri ne 2.5 m, makineri,	m ³	750.00

2	3.331	Gabiona me rrjete teli te zinguar e gure kave 1x1x1 m	m ³	98.00
3	3.111	Mure betoni C 12/15	m ³	150.00
4	2.262/5	Shtrese betoni C20/25	m ³	120.00
5	1.85/p	Pergatitje hekur betoni i zakonshem Ø 6 - 10 mm2	ton	7.00
6	1.86/p	Pergatitje hekur betoni i zakonshem Ø > 12 mm2	ton	4.00
Shuma A				
B - Ndertimi Tombinove rrethore				
1	3.68/a	Germim themel (gropa) sip10-30m ² , shkemb bute, h= 2.5 m, makineri	m ³	80.00
2	3.183/a	Shtrese zhavor lumi t=10cm	m ²	100.00
3	An-8	Mbushje me cakell	m ³	90.00
4	3.366	Tombino me tuba betoni Ø 800, mbi shtrese betoni	ml	80.00
5	3.244	Struktura monolite betoni C 20/25 (Këmish për tubat)	m ³	50.00
6	3.244	Struktura monolite betoni C 20/25 (pusetat, muret mbajt.)	m ³	60.00
Shuma B				
Shuma III (A+B)				

		IV-Sinjalitika		
1	3.936/1	Tabela trekendore normal me A = 90	cope	20.00
2	3.955	FV tabela te ndryshme rrugore D=60cm	cope	6.00
3	An91	Panele plotesues I sinjalistikes rrethore normal 50x25	m ²	5.00
4	An59	Sinjale "emër rruge" LxH normal 80x25	m ²	5.00
5	An1	Guardrail- N2 anesore me 2 valez. ne 1 ane , W2 + aksesor	ml	42.00
Shuma IV				

STUDIO E PROJEKTIMIT
NG STRUCTURES SHPK

MIRATOI
KRYETARI I BASHKISË
ADRIATIK ZOTKAJ