



BASHKIA BERAT

PREVENTIV PUNIMESH

Objekti: Ndertimi i shpatullave te Ures se Lapardhas 2

Nr	Analize	Emertimi	Njesi	Sasi	Cmimi	Vlera
1	2.3	Germim dheu themele e plinta me $b > 2m$, ekskavator me zinxhir 0.5m ³ ,shkarkimi ne auto	m ³	844		
2	AN	Shpim me sonde Ø 0.8 m, ~ 15 m	ml	120		
3	3.244	Struktura monolite betoni C 20/25	m ³	72		
4	3.248	Struktura monolite betoni me çakell C 30/37	m ³	183		
5	3.289	F V hekur betoni periodik, Ç- 5, Ø > 12mm	ton	32.3		
6	3.211	Shtrese çakelli mbeturine kave t=20cm, perhapur e ngjeshur me makineri	m ²	97		
7	3.212/d	Shtrese stabilizant t=20cm	m ²	97		
8	3.331	Gabiona me rrjete teli te zinguar e gure kave 1x1x1 m	m ³	50		
		SHUME				
		TVSH				
		TOTAL				