

PREVENTIV TOTAL

Objekti: Ndertim, Sistemim, Asfaltim i Rrugeve te Brendshme, Bashkia Belsh

Nr	Nr. an.	Emertimi i Punimeve	Njesia	Sasia	Cmimi	Vlera
		1. PUNIME GERMIMI				
1	3.89/b	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi > 2 m, toke zak, kategoria III, me shk ne mjet	m3	3,013.00		
2	3.158/5a	Transport dheu me auto deri 5.0 km	m3	3,013.00		
		SHUMA 1				
		2. PUNIME SHITRESASH				
3	3.164/1b	Mbushje me cakell e gur gurore ne trupin e rruges, perhapur e ngjeshur me makineri, per profilim	m3	3,680.00		
4	3.211	Shtrese cakelli mbeturine kave t=20cm, perhapur e ngjeshur makineri	m2	7,700.00		
5	3.212/a	Shtrese stabilizant t=5cm (Per Bankine)	m2	5,160.00		
6	3.212/b	Shtrese stabilizant t=10cm	m2	16,450.00		
		SHUMA 2				
		3. PUNIME ASFALTIMI				
7	3.222/2	Shtrese binderi me granil gur kave,6cm,me makineri	m2	11,860.00		
		SHUMA 3				
		4. PUNIME BETONI E BETONARMEJE				
8	3.244/1	Struktura te holla monolite betoni C 20/25	m3	32.00		
		SHUMA 4				
		5. NDERTIMI I VEPRAVE TE ARTIT + KANALIZIME				
9	3.396/1	Mbushje me zhavorr per tombino	m3	170.00		
10	3.363	Tombino me tuba betoni Ø 400, mbi shtrese betoni	m	61.00		
11	3.365	Tombino me tuba betoni Ø 600, mbi shtrese betoni	m	32.00		
		SHUMA 5				
		Shuma Analiza				
		Shuma me TVSH (20%)				
		Totali				

Projektues:

ZetaKonsult sh.p.k.

Ing.Lorenc Hoxha

PREVENTIV

**Objekti: Ndertim, Sistemim, Asfaltim i Rrugeve te Brendshme, Bashkia Belsh
Rruga Turbull L=492 ml**

Nr	Nr. an.	Emertimi i Punimeve	Njesia	Sasia	Cmimi	Vlera
		1. PUNIME GERMIMI				
1	3.89/b	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi > 2 m, toke zak, kategoria III, me shk ne mjet	m3	1,128.00		
2	3.158/5a	Transport dheu me auto deri 5.0 km	m3	1,128.00		
		SHUMA 1				
		2. PUNIME SHITESASH				
3	3.164/1b	Mbushje me cakell e gur gurore ne trupin e rruges, perhapur e ngjeshur me makineri, per profilim	m3	650.00		
4	3.211	Shtrese çakelli mbeturine kave t=20cm, perhapur e ngjeshur makineri	m2	2,400.00		
5	3.212/a	Shtrese stabilizant t=5cm (Per Bankine)	m2	800.00		
6	3.212/b	Shtrese stabilizant t=10cm	m2	2,400.00		
		SHUMA 2				
		3. PUNIME ASFALTIMI				
7	3.222/2	Shtrese binderi me granil gur kave,6cm,me makineri	m2	1,650.00		
		SHUMA 3				
		4. PUNIME BETONI E BETONARMEJE				
8	3.244/1	Struktura te holla monolite betoni C 20/25 (kanal+ kunete + mure)	m3	5.00		
		SHUMA 4				
		5. NDERTIMI I VEPRAVE TE ARTIT + KANALIZIME				
9	3.396/1	Mbushje me zhavorr per tombino	m3	40.00		
10	3.363	Tombino me tuba betoni Ø 400, mbi shtrese betoni	m	15.00		
11	3.365	Tombino me tuba betoni Ø 600, mbi shtrese betoni	m	10.00		
		SHUMA 5				
		Shuma Analiza				
		Shuma me TVSH (20%)				
		Totali				

Projektues:
ZetaKonsult sh.p.k.
Ing.Lorenc Hoxha

PREVENTIV

**Objekti: Ndertim, Sistemim, Asfaltim i Rrugeve te Brendshme, Bashkia Belsh
Rruga Shkendi L=650 ml**

Nr	Nr. an.	Emertimi i Punimeve	Njesia	Sasia	Cmimi	Vlera
		1. PUNIME GERMIMI				
1	3.89/b	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi > 2 m, toke zak, kategoria III, me shk ne mjet	m3	1,351.00		
2	3.158/5a	Transport dheu me auto deri 5.0 km	m3	1,351.00		
		SHUMA 1				
		2. PUNIME SHITESASH				
3	3.164/1b	Mbushje me cakell e gur gurore ne trupin e rruges, perhapur e ngjeshur me makineri, per profilim	m3	800.00		
4	3.211	Shtrese çakelli mbeturine kave t=20cm, perhapur e ngjeshur makineri	m2	3,000.00		
5	3.212/a	Shtrese stabilizant t=5cm (Per Bankine)	m2	1,000.00		
6	3.212/b	Shtrese stabilizant t=10cm	m2	3,000.00		
		SHUMA 2				
		3. PUNIME ASFALTIMI				
7	3.222/2	Shtrese binderi me granil gur kave,6cm,me makineri	m2	2,100.00		
		SHUMA 3				
		4. PUNIME BETONI E BETONARMEJE				
8	3.244/1	Struktura te holla monolite betoni C 20/25	m3	10.00		
		SHUMA 4				
		5. NDERTIMI I VEPRAVE TE ARTIT + KANALIZIME				
9	3.396/1	Mbushje me zhavorr per tombino	m3	50.00		
10	3.363	Tombino me tuba betoni Ø 400, mbi shtrese betoni	m	15.00		
11	3.365	Tombino me tuba betoni Ø 600, mbi shtrese betoni	m	8.00		
		SHUMA 5				
		Shuma Analiza				
		Shuma me TVSH (20%)				
		Totali				

Projektues:
ZetaKonsult sh.p.k.
Ing.Lorenc Hoxha

PREVENTIV**Objekti: Ndertim, Sistemim, Asfaltim i Rrugeve te Brendshme, Bashkia Belsh
Rruga Idriz, L=1000 ml**

Nr	Nr. an.	Emertimi i Punimeve	Njesia	Sasia	Cmimi	Vlera
		1. PUNIME SHTRESASH				
1	3.164/1b	Mbushje me cakell e gur gurore ne trupin e rruges, perhapur e ngjeshur me makineri, per profilim	m3	900.00		
2	3.212/a	Shtrese stabilizant t=5cm (Per Bankine)	m2	1,600.00		
3	3.212/b	Shtrese stabilizant t=10cm	m2	5,600.00		
		SHUMA 1				
		2. PUNIME ASFALTIMI				
4	3.222/2	Shtrese binderi me granil gur kave,6cm,me makineri	m2	4,150.00		
		SHUMA 2				
		3. PUNIME BETONI E BETONARMEJE				
5	3.244/1	Struktura te holla monolite betoni C 20/25	m3	7.00		
		SHUMA 3				
		4. NDERTIMI I VEPRAVE TE ARTIT + KANALIZIME				
6	3.396/1	Mbushje me zhavorr per tombino	m3	30.00		
7	3.363	Tombino me tuba betoni Ø 400, mbi shtrese betoni	m	6.00		
8	3.365	Tombino me tuba betoni Ø 600, mbi shtrese betoni	m	6.00		
		SHUMA 4				
		Shuma Analiza				
		Shuma me TVSH (20%)				
		Totali				

Projektues:**ZetaKonsult sh.p.k.****Ing.Lorenc Hoxha**

PREVENTIV

Objekti: Ndertim, Sistemim, Asfaltim i Rrugeve te Brendshme, Bashkia Belsh
Rruga Shkoze, L=700 ml

Nr	Nr. an.	Emertimi i Punimeve	Njesia	Sasia	Cmimi	Vlera
		1. PUNIME SHTRESASH				
1	3.164/1b	Mbushje me cakell e gur gurore ne trupin e rruges, perhapur e ngjeshur me makineri per profilim	m3	480.00		
2	3.212/a	Shtrese stabilizant t=5cm (Per Bankine)	m2	1,200.00		
3	3.212/b	Shtrese stabilizant t=10cm	m2	3,150.00		
		SHUMA 1				
		2. PUNIME ASFALTIMI				
4	3.222/2	Shtrese binderi me granil gur kave,6cm,me makineri	m2	2,260.00		
		SHUMA 2				
		Shuma Analiza				
		Shuma me TVSH (20%)				
		Totali				

Projektues:

ZetaKonsult sh.p.k.

Ing.Lorenc Hoxha

PREVENTIV

Objekti: Ndertim, Sistemim, Asfaltim i Rrugeve te Brendshme, Bashkia Belsh
Rruga Seferan L=560 ml

Nr	Nr. an.	Emertimi i Punimeve	Njesia	Sasia	Cmimi	Vlera
		1. PUNIME GERMIMI				
1	3.89/b	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi > 2 m, toke zak, kategoria III, me shk ne mjet	m3	534.00		
2	3.158/5a	Transport dheu me auto deri 5.0 km	m3	534.00		
		SHUMA 1				
		2. PUNIME SHITRESASH				
3	3.164/1b	Mbushje me cakell e gur gurore ne trupin e rruges, perhapur e ngjeshur me makineri, per profilim	m3	850.00		
4	3.211	Shtrese çakelli mbeturine kave t=20cm, perhapur e ngjeshur makineri	m2	2,300.00		
5	3.212/a	Shtrese stabilizant t=5cm (Per Bankine)	m2	560.00		
6	3.212/b	Shtrese stabilizant t=10cm	m2	2,300.00		
		SHUMA 2				
		3. PUNIME ASFALTIMI				
7	3.222/2	Shtrese binderi me granil gur kave,6cm,me makineri	m2	1,700.00		
		SHUMA 3				
		4. PUNIME BETONI E BETONARMEJE				
8	3.244/1	Struktura te holla monolite betoni C 20/25	m3	10.00		
		SHUMA 4				
		5. NDERTIMI I VEPRAVE TE ARTIT + KANALIZIME				
9	3.396/1	Mbushje me zhavorr per tombino	m3	50.00		
10	3.363	Tombino me tuba betoni Ø 400, mbi shtrese betoni	m	25.00		
11	3.365	Tombino me tuba betoni Ø 600, mbi shtrese betoni	m	8.00		
		SHUMA 5				
		Shuma Analiza				
		Shuma me TVSH (20%)				
		Totali				

Projektues:
ZetaKonsult sh.p.k.
Ing.Lorenc Hoxha

Lorenc
Hoxha

Digitally signed by
Lorenc Hoxha
Date: 2024.04.19
10:24:55 +02'00'