

PREVENTIV

OBJEKTI: "NDERTIM PARKIMI PER MJETET E PASTRIMIT DHE STREH PER QENTE NE LANDFILLIN BERAT"

INVESTITORI: BASHKIA BERAT

**KRYETARI
ERVIN DEMO**

NR	ANALIZA	LLOJI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
PUNIME GERMIMI						
1	2.27a	Germim themele e plinta me ekskavator	m ³	18		
2	2.37/1a	Transport	m ³	18		
PUNIME BETONIE B/A						
1	2.114	Betonim plinti	m ³	12.5		
2	2.116	Betonim trare themeli C 16/20	m ³	8.2		
3	2.167	F.V hekur betoni Ø 6-10mm	ton	0.45		
4	2.167	F.V hekur betoni Ø >12mm	ton	1.2		
5	2.258	F.V shtrese zhavori nen plinta	m ³	2		
6	2.700.	Shtrese betoni C 12/15 me zgare hekuri	m ³	42		
7	3.206	Shtrese zhavori lumi t=30cm, perhapur e ngj	m ²	207		
PUNUME CATIE						
1	2.256/b	Mbulim çatie me panele sanduich t=3cm	m ²	240		
2	2.256/b	Veshje perimetrale me panele sanduich t=3cm	m ²	85		
3	2.182	F.V konstrukcion metalik	ton	2.1		
4	2.182	F.V konstruk. metalik(Kollon+kontraventina)	ton	0.7		
PUNIME HIDRAULIKE						
1	2.491/a	FV Tuba e rakorderi ujesjellesi PPR d=20~2	ml	100		
2	2.494	Saraçineska 1/2 '	copë	8		
PUNIME ELEKTRIKE						
1	2.480/1	F.V tub plastmasi Ø 14 ~ 17 mm	ml	150		
2	2.485.	F.V priza e celesa me nulifikim	cope	5		
3	2.489.	F.V. siguresa ~ 25 A	cope	10		
4	2.486.	F.V portollampa normale 10 A	cope	5		
5	2.481.2	F.V.percjelles 2.5 mm ²	ml	100		
6	2.481/1	F.V.percjelles 1.5 mm ²	ml	100		
7	2.490/e	F.V Automat kryesor me 24 vende	cope	1		
8	2.487.	Kuti derivacioni plastike	cope	10		
9	2.480/2	F.V tub plastmasi Ø 18-21 mm	ml	50		
10	2.487/a	F.V kuti suport pllaket	cope	10		
PUNIME PER GROPEN E RIPARIMIT						
1	2.27a	Germim themele e plinta me ekskavator	m ³	5.1		
2	2.587	Mur b/arme C16/20	m ³	3		
3	2.167	F.V hekur betoni Ø 6-10mm	ton	0.4		
SHPIM PUSI PER LARJE TE MJETEVE						
1	An	Shpim pusi 30-40m	cope	1		
PUNIME PER STREHEN E QENVE						
1	3.206	Shtrese zhavori lumi t=30cm, perhapur e ngj	m ²	170		
2	2.700.	Shtrese betoni C 12/15 me zgare hekuri	m ³	42		
3	2.182	F.V konstrukcion metalik	ton	1.5		
4	2.256/b	Mbulim çatie me panele sanduich t=3cm	m ²	173		
5	3.793	Rjete teli e zinguar	m ²	102		
				SHUMA TOTALE		0.00
				20% TVSH		0
				SHUMA TOTALE		0.0

