



REPUBLIKA E SHQIPERISE
BASHKIA VLORE
DREJTORIA E URBANISTIKES

MIRATOHET
ERMAL DREDHA

KRYETAR

PERMIRESIMI I KUSHTEVE TE BANIMIT PER KOMUNITETET E VARFRA DHE TE
PAFAVORIZUARA (Permiresimi I kushteve te banesave ekzistuese)
PREVENTIV PUNIMESH

NR.	Nr. Ana.	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLEFTA
1. ALIME METANI						
		A.Punime Banese				
1	2.430/2	Prishje çatie ekzistuese me tjegulla	m2	45		
2	2.37/5b	Transport materiale ndertimi, dheu me auto deri 10.0 km	m3	5,4		

3	2.310/1	Suva brenda mur tulle ~ 4m, me pompe, ll perzier M 25	m2	77		
4	2.404/1	Boje hidroplastike cilesi e larte	m2	77		
5	2,219	Çati vendi e zakonshme me HD~8m,tjegulla marseljeze	m2	60		
6	2.212/a	Ulluk shkarkimi horizontal me PVC 33cm	ml	38		
7	2.209/a	Ulluk shkarkimi vertikal me PVC Ø 120	ml	11,2		
8	2.206/b	Kasete shkarkimi me llamarine bakri 1.0mm	cope	2		
9	2,295	Tavan rrjete teli + suva	m2	35		
10	2.375/2a	Dritare d/alumini dyfi xh.	m2	7,8		
11	2,383	F.V dyer druri	m2	8		
		SHUMA I				0,00
2. ANTIGONI MEÇAJ						
		A.Punime Banese				
1	2,430	Prishje shtrese lluster cemento dysHEMEJE	m2	52		
2	2.267b	Shtrese me pllaka grez importi, 40x40cm	m2	52		
3	2.426/11	Prishje suvatim muri i brendshem	m2	153		
4	2,391	Heqje dyer ekzistuese	m2	8		
5	2,392	Heqje dritare ekzistuese	m2	13		
6	2.37/5b	Transport materiale ndertimi, dheu me auto deri 10.0 km	m3	14		
7	2.310/1	Suva brenda mur tulle ~ 4m, me pompe, ll perzier M 25	m2	153		
8	2.404/1	Boje hidroplastike cilesi e larte	m2	153		
9	2.375/2a	Dritare d/alumini dyfi xh.	m2	13		
10	2,383	F.V dyer druri	m2	8		
		SHUMA II				0,00
3.GJYSH BRAHIMAJ						
		A.Punime Banese				
1	2.430/2	Prishje çatie ekzistuese me tjegulla	m2	63		
2	2.37/5b	Transport materiale ndertimi, dheu me auto deri 10.0 km	m3	10,2		
3	2,219	Çati vendi e zakonshme me HD~8m,tjegulla marseljeze	m2	63		

4	2.212/a	Ulluk shkarkimi horizontal me PVC 33cm	ml	35		
5	2.209/a	Ulluk shkarkimi vertikal me PVC Ø 120	ml	16		
6	2.206/b	Kasete shkarkimi me llamarine bakri 1.0mm	cope	2		
7	2.426/12	Prishje suvatim solete (h<4m)	m2	8,5		
8	2.300/1	Suva solete ~ 4 m, me drejtues, me pompe	m2	8,5		
9	2.426/11	Prishje suvatim muri i brendshem	m2	28		
10	2.310/1	Suva brenda mur tulle ~ 4m, me pompe, ll perzier M 25	m2	28		
11	2.404/1	Boje hidroplastike cilesi e larte	m2	36,5		
		SHUMA III				0,00
4.LAVDI RUNAJ						
		A.Punime Banese				
1	2.430/2	Prishje çatie ekzistuese me tjegulla	m2	55		
2	2.426/1	Prishje mur tulle me pastrim(banja siper)	m3	1		
3	2.426/11	Prishje suvatim muri i brendshem	m2	160		
4	2,430	Prishje shtrese lluster-çimento dysHEMEJE (dhomat dhe guzhina)	m2	40		
5	2,391	Heqje dyer ekzistuese	m2	8		
6	2,392	Heqje dritare ekzistuese	m2	8		
7	2.37/5b	Transport materiale ndertimi, dheu me auto deri 10.0 km	m3	21		
8	2.64/2	Mur me tulla te plota zak, deri 3m, llaç perzier M 25	m3	1		
9	2.310/1	Suva brenda mur tulle ~ 4m, me pompe, ll perzier M 25	m2	160		
10	2,266	Shtrese me pllaka granili te zakonshme, 30x30cm	m2	40		
11	2.404/1	Boje hidroplastike cilesi e larte	m2	120		
12	2,295	Tavan rrjete teli + suva	m2	43		
13	2,219	Çati vendi e zakonshme me HD~8m,tjegulla marseljeze	m2	65		
14	2,212	Ulluk shkarkimi horizontal me llamarine xingat 33cm	ml	29,5		
15	2,209	Ulluk shkarkimi vertikal me llamarine xingat Ø 100	ml	10,5		
16	2.206/b	Kasete shkarkimi me llamarine bakri 1.0mm	cope	2		
17	2.375/2a	Dritare d/alumini dyfi xh.	m2	8		

18	2,383	F.V dyer druri	m2	10,08		
		SHUMA IV				0,00
5.LILJANA XHAXHO - Nartë						
		A.Punime prishje				
1	2.426/1	Prishje pjesshem mur tulle me pastrim	m3	2		
2	2.426/4	Prishje solete b/arme	m3	1,8		
3	2.426/3	Prishje shtresa betoni	m3	6		
4	2.426/11	Prishje suva e brendeshme	m2	24		
5	2.426/12	Prishje suvatim solete	m2	32		
6	2,38	Transport mbeturina ndertimi me karoce dore deri 10m	m3	10		
		SHUMA A				0,00
		B.Punime ndertimi				
7	2,5	Germim e mbushje dheu me krahe K.III per themele,h=1,5	m3	2		
8	2.110	Themel e xokol betoni C- 12/15	m3	2,4		
9	2.117	Kollona monolite b/arme C-16/20 ,h~4m	m3	1,2		
10	2.122/1	Soleta te plota b/arme C 16/20 ,h~4m	m3	1,8		
11	2.166/1a	F V hekur betoni periodik Ø > 12 mm	ton	460		
12	2,258	Nenshtrese zhavorri	m3	6		
13	2.262/3	Shtrese betoni C 12/15	m3	6		
14	2.64/2	Mur me tulla te plota deri ne lartesi 3m,ll. I perzier M.25	m3	1,4		
15	2.310/1	Suva brenda mur tulle ~ 4m, me pompe, ll perzier M 25	m2	62		
16	2.300/1	Suvatim solete h~4m me drejtues, me pompe	m2	40		
17	2.267/a	Shtrese pllaka grez importi	m2	74		
18	2.268/a	Shkalle montazhi mermeri	m2	4,5		
19	2,326	Veshje me pllake majolike	m2	16,5		
20	2,272	Pragje mermeri t=20mm per dritare	m2	2		
21	2,197	Hidroizolim solete me emulsion bitumi dhe 2 k katrama	m2	80		
22	2,375	F.V dritare duralumini tek xham	m2	7,8		

23	2.388/1	F.V dyer te brendshme tamburato te rimesuari	m2	7,6		
24	2.395/a	Dere d/alumini pa xham,me mbushje d/a.	m2	3,2		
25	2,404	Boje hidroplastike cilesia I-re	m2	194		
		SHUMA B				0,00
		C.Punime elektrike				
26	2.480/2	F.V tub plastmasi Ø 18 ~ 21 mm	ml	36		
27	2.481/2	F.V percjelles PV-500 Ø 2.5 mm2	ml	36		
28	2.481/3	F.V percjelles PV-500 Ø 4 mm2	ml	18		
29	2490	F.V kuader ndriçimi	cope	1		
30	2,487	F.V Kutiderivacioni plastike	cope	6		
31	2.485/1	F.V Çeles 1 polar 220V 10A	cope	5		
32	2.485/g	F.V priza shuko brenda murit 2 fazore 25 A	cope	6		
33	2.490/1b	F.V Automat termo/el.manj. diferencial 2P 220V, 16A	cope	1		
34	2,486	F.V Portollampa normale 10 A	cope	6		
35	2,496	Elektroda tokezimi, profil zingato e bakerizuar , L=1.5m	cope	1		
		SHUMA C				0,00
		D.Punime hidrosanitare				
36	2.491/a	F.V Tuba e rakorderi ujesjellesi PPR d=20~25mm, PN 25	ml	24		
37	2.516/1	F.V Tuba e rakorderi PVC	kg	5,6		
38	2,501	F.V WC allafrenga	cope	1		
39	2,495	F.V lavaman porcelani me mishelator	cope	1		
		SHUMA D				0,00
		SHUMA V (A + B+C+D)				0,00
6.PETRAQ VERO - BESTROVË						
		A.Punime prishje				
1	2.426/1	Prishje i pjesshem mur tulle me pastrim	m3	3		
2	2.426/3	Prishje shtresa betoni	m3	3,8		
3	2.426/11	Prishje suva e brendeshme	m2	62		

4	2.426/12	Prishje suvatim solete	m2	17		
5	2,38	Transport mbeturina ndertimi me karoce dore deri 10m	m3	3,6		
		SHUMA A				0,00
		B.Punime ndertimi				
6	2,5	Germim e mbushje dheu me krahe K.III per themele,h=1,5	m3	5		
7	2.110	Themel e xokol betoni C- 12/15	m3	5,2		
8	2.121	Brez b/arme mbi xokol C-16/20	m3	0,8		
9	2.117	Kollona monolite b/arme C-16/20 ,h~4m	m3	1,3		
10	2,121	Brez b/arme mbi mur tulle C-16/20	m3	0,6		
11	2.122/1	Soleta te plota b/arme C 16/20 ,h~4m	m3	2,2		
12	2.166/1a	F V hekur betoni periodik Ø > 12 mm	ton	780		
13	2,258	Nenshtrese zhavorri	m3	2,4		
14	2.262/3	Shtrese betoni C 12/15	m3	2,4		
15	2.64/2	Mur me tulla te plota deri ne lartesi 3m,ll. I perzier M.25	m3	7,8		
16	2.310/1	Suva brenda mur tulle ~ 4m, me pompe, ll perzier M 25	m2	120		
17	2.300/1	Suvatim solete h~4m me drejtues, me pompe	m2	40		
18	2,375	F.V dritare duralumini tek xham	m2	1,5		
19	2,383	F.V dyer te brendshme druri	m2	3,8		
20	2.395/a	Dere d/alumini pa xham,me mbushje d/a.	m2	2,64		
21	2,404	Boje hidroplastike cilesia I-re	m2	160		
		SHUMA B				0,00
		C.Punime elektrike				
22	2.480/2	F.V tub plastmasi Ø 18 ~ 21 mm	ml	30		
23	2.481/2	F.V percjelles PV-500 Ø 2.5 mm2	ml	30		
24	2.481/3	F.V percjelles PV-500 Ø 4 mm2	ml	15		
25	2.490	F.V kuader ndriçimi	cope	1		
26	2,487	F.V Kutiderivacioni plastike	cope	6		
27	2.485/1	F.V Çeles 1 polar 220V 10A	cope	4		

28	2.485/g	F.V priza shuko brenda murit 2 fazore 25 A	cope	6		
29	2.490/1b	F.V Automat termo/el.manj. diferencial 2P 220V, 16A	cope	1		
30	2,486	F.V Portollampa normale 10 A	cope	4		
31	2,496	Elektroda tokezimi, profil zingato e bakerizuar , L=1.5m	cope	1		
		SHUMA C				0,00
		D.Punime hidrosanitare				
32	2.491/a	F.V Tuba e rakorderi ujesjellesi PPR d=20~25mm, PN 25	ml	20		
33	2.516/1	F.V Tuba e rakorderi PVC	kg	5,6		
34	2,504	F.V WC allaturka	cope	1		
35	2,495	F.V lavaman porcelani importi me mishelator	cope	1		
		SHUMA D				0,00
		SHUMA VI (A+B+C+D)				0,00
		SHUMA TOTALE (I - VI)				0,00
		TVSH 20 %				0,00
		SHUMA TOTALE				0,00