



MIRATOI
KRYETARI BASHKISE
TONIN MARINAJ

PREVENTIV I PUNIMEVE

Objekti: Sistemim, asfaltim rruga Boriç i Vogel

		Gjatesia e rruges	Metra	1,719.0		
Nr.	Analiza	Emertimi i Punimeve	Njësia	Sasia	Cmimi	Vlera
1	Punime Germimi					
1	3.7	Shkulje rrenjeve bimeve te vogla	m2	600.0		-
2	3.89/a	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi deri 2 m, toke zak, kategoria III, me shk ne mjet	m3	379.7		-
3	3.45/1	Germim kanalesh ne toke te zakonshme, me krahe, me seksion deri 0.75 m ²	m3	80.0		-
4	3.158/5a	Transport dheu me auto deri 5 km	m3	459.7		-
		Shuma	1			-
2	Punime shtresash rrugore					
1	3.205/2	Shtrese zhavori lumi t=20cm, perhapur e ngjeshur me makineri	m2	8,500.0		-
2	3.212/b	Shtrese stabilizant t=10cm	m2	8,500.0		-
3	3.222/2	Shtrese binderi me granil gur kave,6cm,me makineri	m2	5,500.0		-
4	3.212/a	Shtrese stabilizanti t=5cm bankine	m2	2,800.0		-
		Shuma	2			-
3	Punime te ndryshme					
1	3.243/1	Struktura te holla monolite betoni C 16/20	m3	8.57		-
2	2.426/2	Prishje mure blloqesh betoni (mure rrethues)	m3	2.00		-
		Shuma	3			-
I		Shuma(1-3)	Leke			-
II		TVSH 20 %		20%		-
III		VLERA TOTALE (I + II)	Leke			-

Shenim: Preventivi eshte vleresuar me cmimet e V.K.M. Nr. 216 date 13.04.2023

PROJEKTUESI
LENI-ING SHPK shpk
Ing Nikoll Paluca