



REPUBLIKA E SHQIPERISE
BASHKIA KAMEZ
PREVENTIV

OBJEKTI: Ndertim Rruget Blloku 2 Bathore 7

OBJEKTI : Ndertim Rruga "Margegaj" Bathore7

(L =215ml, basf= 4m,

I PUNIME NE RRUGE						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m ³	86		
2	3.158/5a	Transport dheu me auto 5km	m ³	86		
3	3.164/1b	Mbushje me çakell shkembor+bankine	m ³	107.31		
4	3.211	Shtrese çakelli T=20cm	m ²	860		
5	3.212/b	Shtrese stabilizanti t=10cm	m ²	860		
6	3.222/1	Shtrese binderi 1x5 cm	m ²	860		
7	3.224/1	Shtrese asfaltobetoni me granil guri kave, 3cm, me makineri	m ²	860		
8	3.949/1	Vizime me boje bikomponente 15cm(shirita gjatesor dhe anesor).Termoplastike (paste) anesoret + aksi+vije zime kembesoret	ml	480		
9	3.581	Mbingritje h=0.5 m, Pusete ekzistuese UZ Φ 1.0 m	cope	3		
10	3.934/1	F.v. Tabele rrethi "detyrim" normal me D = 60	cope	2		
SHUMA I						

OBJEKTI : Ndertim Rruga "Shishtavec" Bathore7

(L =215ml, basf= 4m)

I PUNIME NE RRUGE						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m ³	86		
2	3.158/5a	Transport dheu me auto 5km	m ³	86		
3	3.164/1b	Mbushje me çakell shkembor+bankine	m ³	103.2		
4	3.211	Shtrese çakelli T=20cm	m ²	860		
5	3.212/b	Shtrese stabilizanti t=10cm	m ²	860		
6	3.222/1	Shtrese binderi 1x5 cm	m ²	860		
7	3.224/1	Shtrese asfaltobetoni me granil guri kave, 3cm, me makineri	m ²	860		
8	3.949/1	Vizime me boje bikomponente 15cm(shirita gjatesor dhe anesor).Termoplastike (paste) anesoret + aksi+vije zime kembesoret	ml	480		
9	3.581	Mbingritje h=0.5 m, Pusete ekzistuese UZ Φ 1.0 m	cope	3		
10	3.934/1	F.v. Tabele rrethi "detyrim" normal me D = 60	cope	2		
SHUMA I						

OBJEKTI : Ndertim Rruga "Terthore" Bathore7

(L =215ml, basf= 4m)

I PUNIME NE RRUGE						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m ³	86		
2	3.158/5a	Transport dheu me auto 5km	m ³	86		
3	3.164/1b	Mbushje me çakell shkembor+bankine	m ³	103.2		
4	3.211	Shtrese çakelli T=20cm	m ²	860		
5	3.212/b	Shtrese stabilizanti t=10cm	m ²	860		
6	3.222/1	Shtrese binderi 1x5 cm	m ²	860		
7	3.224/1	Shtrese asfaltobetoni me granil guri kave, 3cm, me makineri	m ²	860		

8	3.949/1	Vizime me boje bikomponente 15cm(shirita gjatesor dhe anesor).Termoplastike (paste) anesoret + aksi+vijezeime kembesoret	ml	480		
9	3.581	Mbingritje h=0.5 m, Pusete ekzistuese UZ Φ 1.0 m	cope	3		
10	3.934/1	F.v. Tabele rrethi "detyrim" normal me D = 60	cope	2		
SHUMA I						

OBJEKTI : Ndertim Rruga "Topojan" Bathore7

(L =215ml, B=4.5ml, basf= 4m, 0.5m bankine, KUZ -D=315mm)

I PUNIME NE RRUGE						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m ³	116.1		
2	3.158/5a	Transport dheu me auto 5km	m ³	116.1		
3	3.164/1b	Mbushje me çakell shkembor+bankine	m ³	103.2		
4	3.211	Shtrese çakelli T=20cm	m ²	860		
5	3.212/b	Shtrese stabilizanti t=10cm	m ²	860		
6	3.222/1	Shtrese binderi 1x5 cm	m ²	860		
7	3.224/1	Shtrese asfaltbetoni me granil guri kave, 3cm, me makineri	m ²	860		
8	3.949/1	Vizime me boje bikomponente 15cm(shirita gjatesor dhe anesor).Termoplastike (paste) anesoret + aksi+vijezeime kembesoret	ml	480		
9	3.934/1	F.v. Tabele rrethi "detyrim" normal me D = 60	cope	2		
SHUMA I						0.0

II PUNIME NE KUZ						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m ³	258		
2	3.158/5a	Transport dheu me auto 5km	m ³	258		
3	3.396	Mbushje me cakell pas mureve	m ³	205		
4	3.164/1t	F.V. tuba te Brinjezuar SN-8 d=315 mm (perfshire reren per mbrojtjen e tubit)	ml	212		
5	2.599	F.V. pusete shkarkimi 100x100, h=150, me kapak gize	cope	4		
SHUMA II						
SHUMA I-II						

OBJEKTI : Ndertim Rruga "Shtiqen" Bathore7

(L =215ml, basf= 4m, KUZ -D=315mm)

I PUNIME NE RRUGE						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m ³	86		
2	3.158/5a	Transport dheu me auto 5km	m ³	86		
3	3.164/1b	Mbushje me çakell shkembor+bankine	m ³	103.2		
4	3.211	Shtrese çakelli T=20cm	m ²	860		
5	3.212/b	Shtrese stabilizanti t=10cm	m ²	860		
6	3.222/1	Shtrese binderi 1x5 cm	m ²	860		
7	3.224/1	Shtrese asfaltbetoni me granil guri kave, 3cm, me makineri	m ²	860		
8	3.949/1	Vizime me boje bikomponente 15cm(shirita gjatesor dhe anesor).Termoplastike (paste) anesoret + aksi+vijezeime kembesoret	ml	480		
9	3.934/1	F.v. Tabele rrethi "detyrim" normal me D = 60	cope	2		
SHUMA I						

II PUNIME NE KUZ						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m ³	258		
2	3.158/5a	Transport dheu me auto 5km	m ³	258		
3	3.164/1b	Mbushje me çakell shkembor	m ³	205		
4	3.164/1t	F.V. tuba te Brinjezuar SN-8 d=315 mm (perfshire reren per mbrojtjen e tubit)	ml	212		

5,	2.599	F.V. pusete shkarkimi 100x100, h=150, me kapak gize	cope	4		
SHUMA II						
SHUMA I-II						
OBJEKTI : Ndertim Rruga "Surroj" Bathore7						
(L =215ml, basf= 4m)						
I	PUNIME NE RRUGE					
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m ³	117.21		
2	3.158/5a	Transport dheu me auto 5km	m ³	117.21		
3	3.164/1b	Mbushje me çakell shkembor+bankine	m ³	129		
4	3.211	Shtrese çakelli T=20cm	m ²	860		
5	3.212/b	Shtrese stabilizanti t=10cm	m ²	860		
6	3.222/1	Shtrese binderi 1x5 cm	m ²	860		
7	3.224/1	Shtrese asfaltbetoni me granil guri kave, 3cm, me makineri	m ²	860		
8	3.949/1	Vizime me boje bikomponente 15cm(shirita gjatesor dhe anesor).Termoplastike (paste) anesoret + aksi+vijezeime kembesoret	ml	480		
9	3.581	Mbingritje h=0.5 m, Pusete ekzistuese UZ Φ 1.0 m	cope	3		
10	3.934/1	F.v. Tabele rrethi "detyrim" normal me D = 60	cope	2		
SHUMA I						

OBJEKTI : Ndertim Rruga "Llugaj" Bathore 7

(L = 440 ml, B =7m, basf= 4m,2x0.5kunete, 2x1mtrotuar,)

J	An.	Emertimi i Punimeve	Njesia	Sasia	Cmimi	Vlera
I	PUNIME NE RRUGE					
1	3.139	Germim dheu me eskavator	m ³	176		
2	3.158/5a	Transport dheu me auto 5km	m ³	176		
3	3.164/1b	Mbushje me çakell shkembor	m ³	528		
4	2.37/5a	Transport çakelli me auto 5km	m ³	528		
5	3.211	Shtrese çakelli T=20cm	m ²	1760		
6	3.212/b	Shtrese stabilizanti t=10cm	m ²	1760		
7	3.222/1	Shtrese binderi 1x5 cm	m ²	1760		
8	3.224/1	Shtrese asfaltbetoni me granil guri kave, 3cm, me makineri	m ²	1760		
9	2,111	Mure betoni C12/15(themel,xokol betoni)	m ³	154		
10	3.288	F.V Hekur betoni I zakonshem O > 10 mm	ton	4.2		
11	3.581	Mbingritje h=0.5 m, Pusete ekzistuese UZ Φ 1.0 m	cope	9		
12	3.558	Spostim shtylle elektrike (Cmontim dhe montim shtylle elektrike prej betoni perfshire linjat dhe aksesoret)	cope	4		
13	2.426/2	Prishje mure me blloqe + transport	m ³	92		
14	3.949/1	Vizime me boje bikomponente 15cm	ml	1030		
15	3.934/1	F.v. Tabele rrethi "detyrim" normal me D = 60	cope	3		
SHUMA I						0
II	PUNIME NE KUB					
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m ³	352		
2	3.158/5a	Transport dheu me auto 5km	m ³	352		
3	3.164/1b	Mbushje me çakell shkembor	m ³	272		
4	3.164/1t	F.V. tuba te Brinjezuar SN-8 d=315 mm (perfshire reren per mbrojtjen e tubit)	ml	862		
5	2.262/4	Shtrese betoni c 16/20Kunete betoni M - 200	m ³	43.1		
6	2.342	Pusete shiu 40 x 60, h = 100 cm, me kapak gize	cope	30		
SHUMA II						
III	PUNIME TROTUARE(2*1 m)					
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m ³	44		
2	3.158/5a	Transport dheu me auto 5km	m ³	44		
3	3.164/1b	Mbushje me çakell shkembor	m ³	132		

4.	3.208	Shtrese çakelli t=10cm, makadam, perhapur e ngjeshur me makineri	m ²	572		
5	3.212/b	Shtrese stabilizanti ne trotuar T=10cm	m ²	572		
6	3.616/a	F V bordura betoni 15x25cm	ml	880		
7	2.262/4	Beton per fiksime bordure C16/20	m ³	26.4		
8	3.620	Trotuar, me 6 cm beton, me pllaka	m ²	545		
		SHUMA III				
IV		PUNIME PER NDRICIMIN				
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.654/1	F.V. Tub korrogato Ø80 per telefonine	ml	440		
2	3.654/1	F.V. Tub korrogato Ø80 per elektrikun, ndriçimin	ml	440		
3	3.170	F V pusete elektrike kontrolli PVC 40x40x40cm	cope	12		
4	An-19	F.v puseta betoni me kapak gize 80x80x100mm	cope	2		
5	3.139	Germime dheu me ekskavator me goma	m ³	88		
6	3.158/5a	Transport dheu me auto 5km	m ³	88		
7	2.261	Mbushje me rere	m ³	52.8		
8	3.353	Mbushje me shkemb te germuar me pare	m ³	35.2		
9	2.37/5a	Transport cakull me auto 5km	m ³	35.2		
		SHUMA IV				
		SHUMA J				
		TOTALI				
		TVSH 20%				
		TVSH TOTALE				

shenim : preventivi eshte hartuar ne baze te vkm 216 date 13.04.2023

Preventivues:

Ing. Eglantina Disha

Drejtori P.I-se

Ing. Flora MUÇA

