

**MIRATOI  
KRYETARI  
BENET BECI**  
Perfaqesuar me vendim delegimi  
**ZV. KRYETAR  
ONID BEJLERI**

**PREVENTIV PA CMIME**

**Objekti: " Rikonstruksion rruga "Ernest Bushati "**

Nr	Nr AN	EMERTIMI I PUNIMEVE	Njesia	Sasia	Cmimi	Vlera
	<b>I</b>	<b>PUNIME NE RRUGE</b>				
1	2.426/2	Prishje mure me bloqe	m3	15	-	-
2	3.89/a	Germim dheu me ekskavator 0.25 m <sup>3</sup> , toke zak, kategoria III, me shk ne mjet	m3	250	-	-
3	2.37/5a	Transport materiale ndertimi, dheu me auto deri 5.0 km	m3	250	-	-
4	2.426/2	Prishje mure me bloqe	m3	7	-	-
5	3.211	Shtrese çakelli mbeturine kave t=20cm, perhapur e ngjeshur makineri	m <sup>2</sup>	843	-	-
6	3.212/b	Shtrese stabilizanti 10cm per rrugen	m <sup>2</sup>	843	-	-
7	3.222/1	Shtrese binderi me granil gur kave,5cm,me makineri	m <sup>2</sup>	703	-	-
8	3.226/1	Shtrese asfaltobetoni me granil guri kave, 4cm, me makineri	m <sup>2</sup>	703	-	-
9	2.262/3	Shtrese betoni C 12/15 per kunetat	m <sup>3</sup>	14	-	-
		<b>Shuma I</b>			-	-
	<b>II</b>	<b>PUNIME TROTUARI</b>			-	-
1	3.183/a	Shtrese zhavori t=10cm	m2	201	-	-
2	3.618	FV Bordura betoni 20x35 cm	ml	561	-	-
3	3.620	Trotuar, me 6 cm beton, me pllaka	m2	201	-	-
4	3.396	Mbushje me cakell	m3	35.0	-	-
5	3.240	Betoni C 12/15 per fiksime bordure	m3	23.00	-	-
6	3.243	Struktura monolite betoni C 16/20 per themel	m3	8.00	-	-
7	2.64/2	Mur me tulla te plota zak, deri 3m, llaç perzier M 25	m3	9.00	-	-
8	2.334	Suva e zakonshme fasade mur tulle lartesi mbi 8 m	m2	20.00	-	-
		<b>Shuma II</b>			-	-
	<b>III</b>	<b>PUNIME KUB</b>			-	-
1	3.89/a	Germim dheu me ekskavator 0.25 m <sup>3</sup> , toke zak, kategoria III, me shk ne mjet	m3	116	-	-
2	2.37/5a	Transport dheu me auto deri 5 km	m3	60	-	-
3	3.164/1a	Mbushje me material te germuar	m3	37	-	-
4	3.164/1t	F V tuba te brinjezuar HDPE SN8 d=315 mm	ml	282	-	-
5	2.342	puseta shiu 40x60 h=1m, me kapak gize	cope	12	-	-
		<b>Shuma III</b>			-	-
	<b>IV</b>	<b>PUNIME KUZ</b>			-	-
1	3.89/a	Germim dheu me ekskavator 0.25 m <sup>3</sup> , toke zak, kategoria III, me shk ne mjet	m3	141	-	-
2	2.37/5a	Transport dheu me auto deri 5 km	m3	60	-	-
3	3.164/1a	Mbushje me material te germuar	m3	60	-	-
4	3.164/1t	F V tuba te brinjezuar HDPE SN8 d=315 mm	ml	270	-	-
5	2.599	F.V. pusete shkarkimi 100x100, h=150, me kapak gize	cope	5	-	-
6	3.581	Mbingritje h=0.5 m, Pusete ekzistuese UZ Φ 1.0 m	cope	1	-	-
		<b>Shuma IV</b>			-	-
	<b>V</b>	<b>PUNIME PER UJESJELLES</b>			-	-
1	3.89/a	Germim dheu me ekskavator 0.25 m <sup>3</sup> , toke zak, kategoria III, me shk ne mjet	m <sup>3</sup>	45	-	-
2	3.158/5a	Transport dheu me auto deri 5 km	m <sup>3</sup>	45	-	-

3	2.261	Shtrese rere per tuba	m3	16	-	-
4	2.258	Nenshtrese zhavori	m3	16	-	-
5	2.336	Pusete shkarkimi 80 x 80, h = 100 cm	cope	10	-	-
6	2.491/g	F.V Tuba e rakorderi ujesjellesi PE d=90mm, PN 16	ml	278	-	-
7	2.491/c	F.V Tuba e rakorderi ujesjellesi PE d=32mm, t = 2.4 mm, PN 10	ml	700	-	-
8	An	Lidhje me rrjetin ekzistues te linjes se Ujesjellesit	cope	1	-	-
9	An	Kaseta llamarin 60x80x20	cope	5	-	-
10	2.512/6	F.V Kolektor shpendares 1 1/4"	cope	5	-	-
11	2.494/3	F.V saracineska bronzi Ø 1 1/4 " = 32 mm	cope	20	-	-
		<b>shuma V</b>			-	-
	<b>VI</b>	<b>PUNIME NDRICIMI RRUGOR</b>			-	
1	An.	F.V. Kabell Cu 5x6 mm2 FG16OR16	ml	400	-	0
2	An.	F.V. Kabell Cu 3x2.5 mm2 FG16OR17	ml	36	-	0
3	An.	F.V.Aksesore shtyllore(qafore) per terheqje me nje ose dy krahe D=140-250mm	cope	12	-	0
4	An.	F.V.Tel celiku I xinkuar 3,5mm2	ml	400	-	0
5	An.	F.V.Fasheta plastike S SH EN 62275:2009 (8/150mm	cope	400	-	0
6	An.	F.V.Kuti shperndarese metalike 200x150x100mm IP 65, me aksesore per montim ne shtylle BA	cope	9	-	0
7	An.	F.V.Panel komandimi, mbrojtje ndricimi dhe matje energjie 3 fazore	cope	1	-	0
8	An.	F.V.Ndricues rrugor LED 120 W / 3000K	cope	9	-	0
9	An.	F.V. Krah xinkat harkor 1mx1m me aksesore e fasheta metalike per montim ne shtylle BA	cope	9	-	0
		<b>Shuma VI</b>			-	<b>0</b>
	<b>VII</b>	<b>PUNIME SINJALISTIKE</b>			-	
1	3.949/1	Vizime me boje bikomponente me gjeresi 15 cm	ml	561	-	0.00
2	3.949	Vizime me boje bikomponente	m2	5	-	0.00
3	3.934/1	F.v. Tabele rrethi "detyrim" normal me D = 60	cope	2	-	0.00
		<b>Shuma VII</b>			-	-
		<b>SHUMA</b>			-	-
		<b>FONDI REZERVE 3%</b>			-	-
		<b>SHUMA</b>			-	-
		<b>TVSH 20 %</b>			-	-
		<b>TOTALI</b>			-	-

**PREVENTIVOI**  
**"Novatech Studio" shpk**  
**Ing.Emil Nova**