



REPUBLIKA E SHQIPERISE
BASHKIA VLORE
DREJTORIA E URBANISTIKES

MIRATOI
KRYETARI I BASHKISE VLORE
ERMAL DREDHA

RIKONSTRUKSIONI I RRUGES NE VAZHDIM TE 7 PALLATEVE

PREVENTIV PUNIMESH

NR.	Nr. An.	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLEFTA
Rruga vazhdimi i 7 pallateve						
A-Punime Ndertimi						
1	3.107/b	Germim dheu me ekskavator, 1.0 m ³ , ne kanale gjeresi > 2 m, toke zak, kategoria IV, me shk ne toke	m3	866,3		0
	2.37/5a	Transport materiale ndertimi, dheu me auto deri 5.0 km	m3	866,3		0
2	3.164/1b	Mbushje me cakell e gur gurore ne trupin e rruges, perhapur e ngjeshur me makineri	m3	400,0		0
3	3.212/c	Shtrese stabilizant t=15cm	m2	2.000,0		0
4	2.262/4a	Shtrese betoni kufizues asfalti C 20/25	m3	25,6		0
5	3.222/2	Shtrese binderi me granil gur kave,6cm,me makineri	m2	1.600,0		0
6	3.226/1	Shtrese asfaltobetoni me granil guri kave, 4cm, me makineri	m2	1.600,0		0
7	3,942	Vijezim shirita gjatesor dhe anesor me gjeresi 12 cm. Bikoponente (sprajt)	ml	1.000,0		0
Shuma A						0
B-Punime Ndricimi						
8	3.169	F.v. Shtylla metalike per ndricim, H=7ml, d=160mm	cope	14,0		0
9	3,168	FV krah shtylla metalike KRH - MSI 1500/1500/10	cope	14,0		0
10	3,175	F.v. Ndricues Smart VP CL1 CR M-S 250W G.G. FAE 44004, me llampe 250W 230V	cope	14,0		0
11	An.El 5	F.V Kabell fror 3x1,5	ml	367,0		0
12	2,546	F.V. Panel metalik IP65(700x550x250mm)	ml	1,0		0
13	3,182	F.v elektroda tokezimi te zinguara 50x3mm, L=150	cope	14,0		0

14	An.El 3	Tel PV 16mm	ml	370,0		0
15	3,172	F V kuader komandimi komplet me santeri+fotoelement	cope	1,0		0
16	An.El 4	F.V Morsete, kapak,automat	cope	14,0		0
17	An.El 1	F.V Tub plastik dyshtresor me diameter d=63mm	ml	370,0		0
18	An.El 2	F.V Tub 200 mm (per indeksimin e shtyllave)	ml	14,0		0
19	4.142/2.29	F.V.kabllo kontrolli Cu te armuar, ne toke, 4x4 mm2	ml	370,0		0
20	3,176	F.v. Pusete plastike 40x40x40, me kapak te forte RIC 1084+1086	cope	14,0		0
SHUMA B						0
C-Punime Kanali Anesor						
21	3.101/b	Germim dheu me ekskavator zingjir, 0.5 m ³ , ne kanale gjeresi > 2 m, toke zak, kategoria IV, me shk ne mjet	m3	130		0
22	2.37/5a	Transport materiale ndertimi, dheu me auto deri 5.0 km	m3	130		0
23	2,447	Kallepe per mure b/a	m2	605		0
24	2,109	Themel e xokol betoni C 12/15	m3	132,5		0
25	2,166	F V hekur betoni periodik Ø 6 - 10 mm	ton	5,3		0
SHUMA C						0
D-Punime Muri Mbajtës						
26	3.107/b	Germim dheu me ekskavator, 1.0 m ³ , ne kanale gjeresi > 2 m, toke zak, kategoria IV, me shk ne toke	m3	60,0		0
27	2.37/5a	Transport materiale ndertimi, dheu me auto deri 5.0 km	m3	60,0		0
28	2,587	Mur betoni C 20/25	m3	6,6		0
29	2.166/1a	F V hekur betoni periodik Ø > 12 mm	ton	0,7		0
SHUMA D						0
SHUMA						0
T.V.SH. 20%						0
TOTALI ME T.V.SH.						0

**PUNOI: Ing DARJAN HUDHRA
DR. KLAUDIO MEHMETAJ**