

PREVENTIV

Objekti: Sistemim Asfaltim Rruga Fshati Brezhdan, Lagja Reçe
Bashkia Dibër

Nr.	NR.AN	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	ÇMIMI	VLERA
1		PUNIME GERMIMI DHE MBUSHJE NE RRUGE				
1	3.104/b	Germim dheu me ekskavator 0.5 m ³ , b > 2 m, toke zak, kategoria IV, me shk ne mjet (prishje e shtreses egzistuese t=10 cm)	m ³	1,100.00		
2	An-9	Mbushje me zhavor ne trupin e rruges, perhapur e ngjeshur me makineri (seksionim +kasonete)	m ³	245.00		
3	3.158/1a	Transport dheu me auto deri 1.0 km	m ³	1,100.00		
		Shuma 1				
2		PUNIME ASFALTIMI				
1	An.164/1a	Shtresa me cakell e gur gurore,perhapur e ngjeshur me makineri ne shtresa cdo 20 cm	m ³	550.00		
2	3.212/b	Shtrese stabilizant 10 cm	m ²	2,650.00		
3	3.212/b	Shtrese stabilizant 10 cm per bankine	m ²	550.00		
4	3.229/1	Shtrese binderi me zall lavatrice, 5cm, me makineri	m ²	2,650.00		
5	3.231/1	Shtrese asfaltobetoni me zall lavatrice, 3cm, me makineri	m ²	2,650.00		
		Shuma 2				
3		PUNIME PER TOMBINO DHE KANALE BETONI				
		BOX BETONARME 4X2 Prog. 0+407m				
1	3.396/1	Mbushje me zhavorr (nenshtrese)	m ³	100.00		
2	3.240	Struktura monolite betoni C 12/15, per nenshtrese	m ³	2.60		
3	3.245	Struktura monolite betoni C 25/30, per tombinot katrore	m ³	12.20		
4	3.245	Struktura monolite betoni C 25/30, per anet e BOX-it	m ³	27.20		
5	3.245	Struktura monolite betoni C 25/30, per Bordurat	m ³	3.30		
6	3.289	F V hekur betoni Ç-5 Ø > 12mm	ton	2.78		
7	3.624	H / Izolim me emulsion, 2 duar bitum	m ²	52.00		
		Tombino				
8	3.244	Struktura monolite betoni C 20/25 (mure, puseta)	m ³	2.00		
9	4.600	Tub Celiku F200+300/6.35mm, L=5ml,P=49.72kg/ml	kg	273.59		
10	3.183/a	Shtrese zhavor lumi t=10cm	m ²	2.97		
		Shuma 3				

4 PUNIME NE SINJALISTIKE					
1	An129	Vijezim shirita gjatesor dhe anesor me gjeresi 15 cm. Akrelike	ml	1,100.00	
2	An139	Vijezim shirita me gjeresi 30 cm, kalim kembesoresh. Akrelike	ml	8.00	
3	An158	FV tabela te ndryshme rrugore D=60cm	copë	5.00	
4	An157	F V tabela rrugore treguese 60x20cm	cope	1.00	
SHUMA 4					
SHUMA TOTALE					
FONDI REZERVE			3%		
SHUMA					
T.V.SH.			20%		
SHUMA ME TVSH					

Shenime: Çmimet e preventivit jane ne baze manualit te çmimeve te vitit 2015.

Preventivues :
ERALD-G SH.P.K

Ing. Gezim Islami

