

Projektuesi: "Engineering Consulting Group" sh.p.k
 Objekti: "Rikonstruksion i rruges ne fshatin Ftterrë ,Bashkia Himarë".

PREVENTIV PUNIMESH

NR.	KODI	EMËRTIMI I PUNIMEVE.	NJËSIA	SASIA	ÇMIMI PA TVSH	VLEFTA PA TVSH
1. PUNIME GERMIMI						
1	3.104/b	Germim dheu me ekskavator zingjir, 0.5 m ³ , ne kanale gjeresi > 2 m, toke zak, kategoria IV, me shk ne mjet	m3	3715	0.00	-
2	3.2	Prerje bime te vogla ø-10cm	m2	1200	0.00	-
SHUMA 1:						-
2. PUNIME DHEU						
3	2.37/5b	Transport materiale ndertimi, dheu me auto deri 10.0 km	m3	6335	0.00	-
4	2.48/an	Germim shkemb i forte me çekiq me ekskavator me zinxhir	m3	4120	0.00	-
SHUMA 2:						-
3. PUNIME SHTRESASH						
5	3.164/1a	Mbushje me material te germuar ne trupin e rruges, perhapur e ngjeshur me makineri	m3	1500	0.00	-
6	3.212/b	Shtrese stabilizant t=10cm	m2	33250	0.00	-
7	3.211	Shtrese çakelli mbeturine kave t=20cm, perhapur e ngjeshur me makineri	m2	33250	0.00	-
8	3.211	Shtrese çakelli mbeturine kave t=20cm, perhapur e ngjeshur me makineri	m2	33250	0.00	-
SHUMA 3:						-
4. ANALIZA TEKNIKE						
9	3.226/1	Shtrese asfaltbetoni me granil guri kave, 4cm, me makineri	m2	33250	0.00	-
10	3.222/2	Shtrese binderi me granil gur kave,6cm,me makineri	m2	33250	0.00	-
SHUMA 4:						-
5. PUNIME TE NDRYSHME						
11	3.616/a	F V bordura betoni 15x25cm	m	2835	0.00	-
SHUMA 5:						-
6. PUNIME SHTRESASH 2						
12	2.262/4	Shtrese betoni C 16/20 (kuneta)	m3	279	0.00	-
SHUMA 6:						-
7. NDERTIMI DHE MIREMBATJE E VEPRAVE TE ARTIT+KANALIZIME						
13	3.365	Tombino me tuba betoni Ø 600, mbi shtrese betoni	m	48	0.00	-
14	3.366	Tombino me tuba betoni Ø 800, mbi shtrese betoni	m	14	0.00	-
15	3.364	Tombino me tuba betoni Ø 500, mbi shtrese betoni	m	6	0.00	-
16	An.1	Pastrim tombino ekzistuese me autobot teknologjik dhe transport me makineri ndihmese DN 500 mm	ore	16	0.00	-
SHUMA 7:						-
8. B. SINJALET HORIZONTALE						
17	3.942	Vijezim shirita gjatesor dhe anesor me gjeresi 12 cm. Bikoponente (sprajt)	ml	19000	0.00	-
SHUMA 8:						-
9. PUNIME BETONI E BETONARMEJE						
18	3.243	Struktura monolite betoni C 16/20	m3	253	0.00	-
19	3.244	Struktura monolite betoni C 20/25	m3	106.5	0.00	-
SHUMA 9:						-
10. PUNIME MURATURE GURI						
20	2.54/2	Mur guri ne lartesi deri 3m me llaç çimento M 25	m3	12	0.00	-
SHUMA 10:						-
11. PUNIME HEKUR BETONI						
21	2.166	F V hekur betoni periodik Ø 6 - 10 mm	ton	4	0.00	-
22	2.166/1a	F V hekur betoni periodik Ø > 12 mm	ton	5.2	0.00	-
SHUMA 11:						-
12. TE NDRYSHME, ELEKTRIKE DHE SINJALISTIKA						



23	3.185	F.V guardrail- N2 anesore me 2 valez. ne 1 ane , W4	ml	140	0.00	-
24	3.936	F.v. Tabela trekendore e vogel me A = 60	copë	14	0.00	-
25	3.933	F.v. Tabela tetekendore e vogel me A-B, 60-20	copë	3	0.00	-
		SHUMA 12:				-
		13. D. SINJALET DHE PAJISJET SHITESHE. NGADALESUESIT E SHPEJTESISE				
26	3.955	FV tabela te ndryshme rrugore D=60cm	copë	2	0.00	-
		SHUMA 13:				-
Shuma Analiza						-
Fondi Rezervë (5.0%)						-
Shuma Analiza + Fondi Rezervë (5.0%)						-
Shuma TVSH (20%)						-
Shuma me TVSH						-
Totali						-

Preventivues: Ing. Ermir ÇUPI



Investitor: Bashkia Himarë



Ermir cupi
 Digitally signed by
 Ermir cupi
 Date: 2024.10.15
 11:39:47 +0200