



REPUBLIKA E SHQIPERISE  
BASHKIA KAMEZ  
PREVENTIV

OBJEKTI: Rikonstruksion rruga "Lunxheri" Lakaas							
( L =805ml, B ~ 10m, basfekz= 6m, 2x0.5kunete,2x1.5 trotuar, )+muri rruga "Kozare"							
An.	Emertimi i Punimeve			Njesia	Sasia	Cmimi	Vlera
<b>I PUNIME NE RRUGE</b>							
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA	
1	3.969	Skarifikim shtrese asfalti ekzistues me makineri	m <sup>2</sup>	4852			
2	3.139	Germim dheu me eskavator	m <sup>3</sup>	350			
3	3.158/5a	Transport dheu me auto 5km	m <sup>3</sup>	350			
4	3.164/1b	Mbushje me çakell shkembor	m <sup>3</sup>	250			
5	3.211	Shtrese çakelli T=20cm	m <sup>2</sup>	500			
6	3.212/b	Shtrese stabilizanti t=10cm	m <sup>2</sup>	500			
7	3.222/2	Shtrese binderi 1x6 cm	m <sup>2</sup>	500			
8	3.226/1	Shtrese asfaltobetoni 1x4cm+rampe per ngadalsim shpejtesie(3 rampa)	m <sup>2</sup>	4870			
9	2,111	Mure betoni C12/15(themel,xokol betoni) themel+ mure mbajtes te rruges kozare	m <sup>3</sup>	448.328			
10	3.288	F.V Hekur betoni I zakonshem O > 12 mm	ton	22.6502			
11	3.581	Mbingritje h=0.5 m, Pusete ekzistuese UZ Ø 1.0 m	cope	12			
12	3.949/1	Vizime me boje bikomponente 15cm(shirita gjatesor dhe anesor ).Termoplastike (paste ) anesoret + aksi+vije zime kembesoret	ml	1650			
13	3.934/1	F.v. Tabele rrethi "detyrim" normal me D = 60	cope	10			
<b>SHUMA I</b>							
<b>II PUNIME NE KUB (riparime)</b>							
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA	
1	3.139	Germim dheu me eskavator	m <sup>3</sup>	120			
2	3.158/5a	Transport dheu me auto 5km	m <sup>3</sup>	120			
3	3.396	Mbushje me cakell pas mureve	m <sup>3</sup>	98			
4	3.164/1t	F.V. tuba te Brinjezuar SN-8 d=315 mm	ml	491			
5	2.262/4	Shtrese betoni c 16/20Kunete betoni M - 200	m <sup>3</sup>	110.4			
6	2.342	Pusete shiu 40 x 60, h = 100 cm, me kapak gize	cope	32			
<b>SHUMA II</b>							
<b>III PUNIME TROTUARE( 2x1.5 m dy ane)</b>							
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA	
1	3.139	Germim dheu me eskavator	m <sup>3</sup>	185.15			
2	3.158/5a	Transport dheu me auto 5km	m <sup>3</sup>	185.15			
3	3.164/1b	Mbushje me çakell shkembor	m <sup>3</sup>	277.725			
4	3.208	Shtrese çakelli t=10cm, makadam, perhapur e ngjeshur me makineri	m <sup>2</sup>	2250			
5	3.212/b	Shtrese stabilizanti ne trotuar T=10cm	m <sup>2</sup>	2250			
6	3.616/a	F V bordura betoni 15x25cm	ml	1610			
7	2.262/4	Beton per fiksime bordure C16/20	m <sup>3</sup>	48.300			
8	3.620	Trotuar, me 6 cm beton, me pllaka	m <sup>2</sup>	1799			
9	2,111	mbajtes	m <sup>3</sup>	26			
10	3.288	F V hekur betoni i zakonshem Ø > 12mm	ton	0.312			
11	3.961	F.V. Fidane Peme dekorative	cope	40			
<b>SHUMA III</b>							

**PUNIME PER NDRICIMIN**

NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.654/1	F.V. Tub korrogato Ø80 per telefonine	ml	805		
2	3.654/1	F.V. Tub korrogato Ø80 per elektrikun, ndriçimin	ml	805		
3	3.167	FV shtylla metalike konike ndricimi H=9m PAICC-3	cope	23		
4	3.168	FV krah shtylla metalike KRH - MSI 1500/1500/10	cope	23		
5	3.175	44004,me llampe 250W 230V	cope	23		
6	An	F.V. morsete tre fazore +siguresa+kapak per shtyllen h=7	cope	23		
7	3.182	FV elektroda tokezimi te xinguara 50x3mm L=150cm	cope	23		
8	4.131/3.5	F.V.ne toke kablllo Cu fuqie ÷1000V, me izolim gome e mbulesë plastmasi, te armuar, 4x10mm2	ml	805		
9	2.500	F.V. Percjelles Tokezimi , Cu, S=35mm2, i zhveshur	ml	37		
10	2.548	F. V. Kontator trefazor,380V,40A	cope	2		
11	3.170	F V pusete elektrike kontrolli PVC 40x40x40cm	cope	23		
12	An-19	F.v puseta betoni me kapak gize 80x80x100mm	cope	3		
13	3.172	F V kuader komandimi komplet me santeri+fotoelement	cope	1		
14	2.452	F.V. Kasete Metalike 36 Module	cope	1		
15	3.139	Germime dheu me ekskavator me goma	m³	32		
16	3.158/5a	Transport dheu me auto 5km	m³	32		
17	2.261	Mbushje me rere	m³	20		
18	3.353	Mbushje me shkemb te germuar me pare	m³	10		
		<b>SHUMA IV</b>				
		<b>SHUMA I-V</b>				

**OBJEKTI : Ndertim seg. "Paralel me Lunxherine" Laknas**

( L =45ml, B=5ml, basf= 4m, 0.5m bankine ne dy anet, KUZ -D=315mm)

I	PUNIME NE RRUGE					
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m³	22.5		
2	3.158/5a	Transport dheu me auto 5km	m³	22.5		
3	3.164/1b	Mbushje me çakell shkembor+bankine	m³	33.75		
4	3.211	Shtrese çakelli T=20cm	m²	225		
5	3.212/b	Shtrese stabilizanti t=10cm	m²	225		
6	3.222/1	Shtrese binderi 1x5 cm	m²	180		
7	3.224/1	Shtrese asfaltbetoni me granil guri kave, 3cm, me makineri	m²	180		
8	3.949/1	Vizime me boje bikomponente 15cm(shirita gjatesor dhe anesor ).Termoplastike (paste ) anesoret + aksi+vije zime kembesoret	ml	100		
9	3.934/1	F.v. Tabele rrethi "detyrim" normal me D = 60	cope	1		

**SHUMA I**

II	PUNIME NE KUZ					
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m³	54		
2	3.158/5a	Transport dheu me auto 5km	m³	54		
3	3.396	Mbushje me cakell pas mureve	m³	46		
4	3.164/1t	F.V. tuba te Brinjezuar SN-8 d=315 mm ( perfshire reren per mbrojtjen e tubit )	ml	44		
5	2.599	F.V. pusete shkarkimi 100x100, h=150, me kapak gize	cope	1		
		<b>SHUMA II</b>				
		<b>SHUMA I-II</b>				

**OBJEKTI : Ndertim seg. "Pingul me Durresin" Laknas**

( L1 =100ml, B=5 deri 5.5ml, basf= 4m, 0.5m kub nje ane, trotuar 0.5deri ne 1m nje ane, KUZ -D=315mm)

( L2+L3 =80ml, shtrim me pllaka)

I	PUNIME NE RRUGE					
---	-----------------	--	--	--	--	--

NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m <sup>3</sup>	40		
2	3.158/5a	Transport dheu me auto 5km	m <sup>3</sup>	40		
3	3.164/1b	Mbushje me çakell shkembor	m <sup>3</sup>	108		
4	3.211	Shtrese çakelli T=20cm	m <sup>2</sup>	400		
5	3.212/b	Shtrese stabilizanti t=10cm	m <sup>2</sup>	400		
6	3.222/1	Shtrese binderi 1x5 cm	m <sup>2</sup>	400		
7	3.224/1	Shtrese asfaltbetoni me granil guri kave, 3cm, me makineri	m <sup>2</sup>	400		
8	2,111	Mure betoni C12/15(themel,xokol betoni)	m <sup>3</sup>	26		
9	3.288	F.V Hekur betoni I zakonshem O > 12 mm	ton	0.312		
10	3.949/1	Vizime me boje bikomponente 15cm	ml	210		
11	3.558	Spostim shtylle elektrike (Cmontim dhe montim shtylle elektrike prej betoni perfshire linjat dhe aksesoret)	cope	4		
12	3.934/1	F.v. Tabele rrethi "detyrim" normal me D = 60	cope	2		
<b>SHUMA I</b>						
<b>II PUNIME NE KUB</b>						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m <sup>3</sup>	40		
2	3.158/5a	Transport dheu me auto 5km	m <sup>3</sup>	40		
3	3.396	Mbushje me cakell pas mureve	m <sup>3</sup>	31		
4	3.164/1t	F.V. tuba te Brinjezuar SN-8 d=315 mm ( perfshire reren per mbrojtjen e tubit )	ml	97		
5	2.262/4	Shtrese betoni c 16/20Kunete betoni M - 200	m <sup>3</sup>	2.2		
6	2.342	Pusete shiu 40 x 60, h = 100 cm, me kapak gize	cope	3		
<b>SHUMA II</b>						
<b>III PUNIME TROTUARE( 0.5m deri 1m njera ane)</b>						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m <sup>3</sup>	6.5		
2	3.158/5a	Transport dheu me auto 5km	m <sup>3</sup>	6.5		
3	3.164/1b	Mbushje me çakell shkembor	m <sup>3</sup>	20		
4	3.208	Shtrese çakelli t=10cm, makadam, perhapur e ngjeshur me makineri	m <sup>2</sup>	65		
5	3.212/b	Shtrese stabilizanti ne trotuar T=10cm	m <sup>2</sup>	65		
6	3.616/a	F V bordura betoni 15x25cm	ml	196		
7	2.262/4	Beton per fiksime bordure C16/20	m <sup>3</sup>	2.88		
8	2.109/2	Shtrese betoni trotuari	m <sup>3</sup>	6.5		
<b>SHUMA III</b>						
<b>IV PUNIME NE KUZ</b>						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m <sup>3</sup>	120		
2	3.158/5a	Transport dheu me auto 5km	m <sup>3</sup>	120		
3	3.396	Mbushje me cakell pas mureve	m <sup>3</sup>	111		
4	3.164/1t	F.V. tuba te Brinjezuar SN-8 d=315 mm ( perfshire reren per mbrojtjen e tubit )	ml	97		
5	2.599	F.V. pusete shkarkimi 100x100, h=150, me kapak gize	cope	3		
<b>SHUMA IV</b>						
<b>V PUNIME PER NDRICIMIN</b>						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.654/1	F.V. Tub korrogato Ø80 per telefonine	ml	100		
2	3.654/1	F.V. Tub korrogato Ø80 per elektrikun, ndricimin	ml	100		
3	3.167	FV shtylla metalike konike ndricimi H=9m PAICC-3	cope	5		
4	3.168	FV krah shtylla metalike KRH - MSI 1500/1500/10	cope	5		
5	3.175	FV ndricues Smart VP CL1 CR M-S 250W GG FAE 44004,me llampe 250W 230V	cope	5		
6	An	F.V. morsete tre fazore +siguresa+kapak per shtyllen h=7	cope	5		

7	3.182	F.V. elektroda tokezimi te xinguara 50x5mm L=150cm	cope	5		
8	4.131/3.5	F.V.ne toke kablllo Cu fuqie ÷1000V, me izolim gome e mbulese plastmasi, te armuar, 4x10mm2	ml	100		
9	2.500	F.V. Percjelles Tokezimi , Cu, S=35mm2, i zhveshur	ml	8		
10	2.548	F. V. Kontator trefazor,380V,40A	cope	1		
11	3.170	F V pusete elektrike kontrolli PVC 40x40x40cm	cope	5		
12	An-19	F.v puseta betoni me kapak gize 80x80x100mm	cope	1		
13	3.172	F V kuader komandimi komplet me santeri+fotoelement	cope	1		
14	2.452	F.V. Kasete Metalike 36 Module	cope	1		
15	3.139	Germime dheu me ekskavator me goma	m <sup>3</sup>	40		
16	3.158/5a	Transport dheu me auto 5km	m <sup>3</sup>	40		
17	2.261	Mbushje me rere	m <sup>3</sup>	15		
18	3.353	Mbushje me shkemb te germuar me pare	m <sup>3</sup>	25		
<b>SHUMA V</b>						

( L2+L3 =80ml, shtrim me pllaka)

<b>VI PUNIME Shtrim Pllakash</b>						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m <sup>3</sup>	280		
2	3.158/5a	Transport dheu me auto 5km	m <sup>3</sup>	280		
3	3.164/1b	Mbushje me çakell shkembor	m <sup>3</sup>	48		
4	3.208	Shtrese çakelli t=10cm, makadam, perhapur e ngjeshur me makineri	m <sup>2</sup>	280		
5	3.212/b	Shtrese stabilizanti ne trotuar T=10cm	m <sup>2</sup>	280		
6	3.620	Trotuar, me 6 cm beton, me pllaka	m <sup>2</sup>	320		
7	3.616/a	F V bordura betoni 15x25cm	ml	156		
8	2.262/4	Beton per fiksime bordure C16/20	m <sup>3</sup>	4.8		
<b>SHUMA IV</b>						

<b>VII PUNIME NE KUZ</b>						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m <sup>3</sup>	96		
2	3.158/5a	Transport dheu me auto 5km	m <sup>3</sup>	96		
3	3.396	Mbushje me cakell pas mureve	m <sup>3</sup>	87		
5	3.164/1t	F.V. tuba te Brinjezuar SN-8 d=315 mm ( perfshire reren per mbrojtjen e tubit )	ml	78		
6	2.599	F.V. pusete shkarkimi 100x100, h=150, me kapak gize	cope	2		
<b>SHUMA VII</b>						
<b>SHUMA I-VII</b>						

**OBJEKTI : Ndertim seg. "Pingul me Luren" Laknas**

( L =70ml, B=3.7ml, basf= 3.2m, 0.5m bankine ne dy anet, KUZ -D=315mm)

<b>I PUNIME NE RRUGE</b>						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m <sup>3</sup>	28		
2	3.158/5a	Transport dheu me auto 5km	m <sup>3</sup>	28		
3	3.164/1b	Mbushje me çakell shkembor+bankine	m <sup>3</sup>	42		
4	3.211	Shtrese çakelli T=20cm	m <sup>2</sup>	280		
5	3.212/b	Shtrese stabilizanti t=10cm	m <sup>2</sup>	280		
6	3.222/1	Shtrese binderi 1x5 cm	m <sup>2</sup>	280		
7	3.224/1	Shtrese asfaltbetoni me granil guri kave, 3cm, me makineri	m <sup>2</sup>	280		
8	3.949/1	Vizime me boje bikomponente 15cm(shirita gjatesor dhe anesor ).Termoplastike (paste ) anesoret + aksi+vije zime kembesoret	ml	290		
9	3.934/1	F.v. Tabele rrethi "detyrim" normal me D = 60	cope	2		
<b>SHUMA I</b>						
<b>II PUNIME NE KUZ</b>						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m <sup>3</sup>	84		

2	3.158/5a	Transport dheu me auto 5km	m <sup>3</sup>	84		
3	3.396	Mbushje me cakell pas mureve	m <sup>3</sup>	76		
4	3.164/1t	F.V. tuba te Brinjezuar SN-8 d=315 mm ( perfshire reren per mbrojtjen e tubit )	ml	68		
5	2.599	F.V. pusete shkarkimi 100x100, h=150, me kapak gize	cope	2		
		<b>SHUMA II</b>				
		<b>SHUMA I-II</b>				

**OBJEKTI : Ndertim rruga "Korçe" Laknas**

**( L =140ml, B=6ml, basf= 4m, 0.5m kub nje ane, trot ne dy anet 0.5deri ne 1m, KUZ -D=315mm)**

<b>I PUNIME NE RRUGE</b>						
<b>NR.</b>	<b>Nr.An</b>	<b>PERSHKRIMI I PUNIMEVE</b>	<b>NJESIA</b>	<b>SASIA</b>	<b>CMIMI</b>	<b>VLERA</b>
1	3.139	Germim dheu me eskavator	m <sup>3</sup>	56		
2	3.158/5a	Transport dheu me auto 5km	m <sup>3</sup>	56		
3	3.164/1b	Mbushje me cakell shkembor	m <sup>3</sup>	84		
4	3.211	Shtrese cakelli T=20cm	m <sup>2</sup>	552		
5	3.212/b	Shtrese stabilizanti t=10cm	m <sup>2</sup>	552		
6	3.222/1	Shtrese binderi 1x5 cm	m <sup>2</sup>	552		
7	3.224/1	Shtrese asfaltbetoni me granil guri kave, 3cm, me makineri	m <sup>2</sup>	552		
8	2,111	Mure betoni C12/15(themel,xokol betoni)	m <sup>3</sup>	52		
9	3.288	F.V Hekur betoni I zakonshem O > 12 mm	ton	0.624		
10	3.949/1	Vizime me boje bikomponente 15cm	ml	290		
11	3.558	Spostim shtylle elektrike (Cmontim dhe montim shtylle elektrike prej betoni perfshire linjat dhe aksesoret)	cope	4		
12	3.934/1	F.v. Tabele rrethi "detyrim" normal me D = 60	cope	2		
		<b>SHUMA I</b>				
<b>II PUNIME NE KUB</b>						
<b>NR.</b>	<b>Nr.An</b>	<b>PERSHKRIMI I PUNIMEVE</b>	<b>NJESIA</b>	<b>SASIA</b>	<b>CMIMI</b>	<b>VLERA</b>
1	3.139	Germim dheu me eskavator	m <sup>3</sup>	56		
2	3.158/5a	Transport dheu me auto 5km	m <sup>3</sup>	56		
3	3.396	Mbushje me cakell pas mureve	m <sup>3</sup>	39		
4	3.164/1t	F.V. tuba te Brinjezuar SN-8 d=315 mm ( perfshire reren per mbrojtjen e tubit )	ml	80		
5	2.262/4	Shtrese betoni c 16/20Kunete betoni M - 200	m <sup>3</sup>	5.48		
6	2.342	Pusete shiu 40 x 60, h = 100 cm, me kapak gize	cope	4		
		<b>SHUMA II</b>				
<b>III PUNIME TROTUARE( 0.5m deri 1m dy ane)</b>						
<b>NR.</b>	<b>Nr.An</b>	<b>PERSHKRIMI I PUNIMEVE</b>	<b>NJESIA</b>	<b>SASIA</b>	<b>CMIMI</b>	<b>VLERA</b>
1	3.139	Germim dheu me eskavator	m <sup>3</sup>	18.2		
2	3.158/5a	Transport dheu me auto 5km	m <sup>3</sup>	18.2		
3	3.164/1b	Mbushje me cakell shkembor	m <sup>3</sup>	56		
4	3.208	Shtrese cakelli t=10cm, makadam, perhapur e ngjeshur me makineri	m <sup>2</sup>	182		
5	3.212/b	Shtrese stabilizanti ne trotuar T=10cm	m <sup>2</sup>	182		
6	3.616/a	F V bordura betoni 15x25cm	ml	276		
7	2.262/4	Beton per fiksim bordure C16/20	m <sup>3</sup>	8.4		
8	2.109/2	Shtrese betoni trotuari C16/20	m <sup>3</sup>	18.2		
		<b>SHUMA III</b>				
<b>IV PUNIME NE KUZ</b>						
<b>NR.</b>	<b>Nr.An</b>	<b>PERSHKRIMI I PUNIMEVE</b>	<b>NJESIA</b>	<b>SASIA</b>	<b>CMIMI</b>	<b>VLERA</b>
1	3.139	Germim dheu me eskavator	m <sup>3</sup>	168		
2	3.158/5a	Transport dheu me auto 5km	m <sup>3</sup>	168		
3	3.396	Mbushje me cakell pas mureve	m <sup>3</sup>	154		
4	3.164/1t	F.V. tuba te Brinjezuar SN-8 d=315 mm ( perfshire reren per mbrojtjen e tubit )	ml	137		
5	2.599	F.V. pusete shkarkimi 100x100, h=150, me kapak gize	cope	3		
		<b>SHUMA IV</b>				

**PUNIME PER NDRICIMIN**

NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.654/1	F.V. Tub korrogato Ø80 per telefonine	ml	140		
2	3.654/1	F.V. Tub korrogato Ø80 per elektrikun, ndriçimin	ml	140		
3	3.167	FV shtylla metalike konike ndricimi H=9m PAICC-3	cope	4		
4	3.168	FV krah shtylla metalike KRH - MSI 1500/1500/10	cope	4		
5	3.175	FV ndricues Smart VP CL1 CR M-S 250W GG FAE 44004,me llampe 250W 230V	cope	4		
6	An	F.V. morsete tre fazore +siguresa+kapak per shtyllen h=7	cope	4		
7	3.182	FV elektroda tokezimi te xinguara 50x3mm L=150cm	cope	4		
8	4.131/3.6	F.V Kabell Cu me me fuqi -1000V me izolim gome (4x16mmk)	ml	140		
9	2.500	F.V. Percjelles Tokezimi , Cu, S=35mm2, i zhveshur	ml	6		
10	2.548	F. V. Kontator trefazor,380V,40A	cope	1		
11	3.17	F V pusete elektrike kontrolli PVC 40x40x40cm	cope	4		
12	An-19	F.v puseta betoni me kapak gize 80x80x100mm	cope	1		
13	3.172	F V kuader komandimi komplet me santeri+fotoelement	cope	1		
14	2.452	F.V. Kasete Metalike 36 Module	cope	1		
15	3.139	Germime dheu me ekskavator me goma	m <sup>3</sup>	56		
16	3.158/5a	Transport dheu me auto 5km	m <sup>3</sup>	56		
17	2.261	Mbushje me rere	m <sup>3</sup>	21		
18	3.353	Mbushje me shkemb te germuar me pare	m <sup>3</sup>	35		
		<b>SHUMA V</b>				
		<b>SHUMA I-V</b>				
		<b>TOTALI</b>				
		<b>TVSH 20%</b>				
		<b>TVSH TOTALE</b>				

**SHENIM:** Preventivi eshte hartuar ne baze te VKM nr.216, date 13.04.2023

**Preventivues :**  
**Ing. Hajredin Murgu**



**Drejtori P.I-se**  
**Ing. Flora MUÇA**



**MIRATOI**  
**Rakip SULLI**

**KRYETAR**

