



REPUBLIKA E SHQIPERISE
BASHKIA KAMEZ
PREVENTIV

OBJEKTI : Ndertim Rruga "Jupiteri" Valias

(L = 205 ml, B = 7m, basf=4m,2x0.5kunete, 2x1mtrotuar,)

A	An.	Emertimi i Punimeve	Njesia	Sasia	Cmimi	Vlera
I	PUNIME NE RRUGE					
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m ³	71.75		
2	3.158/5a	Transport dheu me auto 5km	m ³	71.75		
3	3.164/1b	Mbushje me çakell shkembor+bankine	m ³	51.8		
4	3.209	Shtrese çakelli T=10cm	m ²	820		
5	3.212/b	Shtrese stabilizanti t=10cm	m ²	820		
6	3.222/2	Shtrese binderi 1x6 cm	m ²	820		
7	3.226/1	Shtrese asfaltobetoni 1x4cm	m ²	820		
8	2,111	Mure betoni C12/15(themel,xokol betoni) themel+ mure mbajtes	m ³	9.36		
9	3.288	F.V Hekur betoni I zakonshem O > 12 mm	ton	1.2		
10	3.581	Mbingritje h=0.5 m, Pusete ekzistuese UZ Ø 1.0 m	cope	2		
11	3.558	Spostim shtylle elektrike (Cmontim dhe montim shtylle elektrike prej betoni perfshire linjat dhe aksesoret)	cope	2		
12	3.949/1	Vizime me boje bikomponente 15cm	ml	410		
13	3.934/1	F.v. Tabele rrethi "detyrim" normal me D = 60	cope	3		
		SHUMA I				
II	PUNIME NE KUB					
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m ³	143.5		
2	3.158/5a	Transport dheu me auto 5km	m ³	143.5		
3	3.164/1b	Mbushje me çakell shkembor	m ³	106.5		
4	3.164/1t	F.V. tuba te Brinjezuar SN-8 d=315 mm (perfshire reren per mbrojtjen e tubit)	ml	401		
5	2.262/4	Shtrese betoni c 16/20Kunete betoni M - 200	m ³	19.5		
6	2.342	Pusete shiu 40 x 60, h = 100 cm, me kapak gize	cope	14		
		SHUMA II				
III	PUNIME TROTUARE(2*1 m)					
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m ³	41		
2	3.158/5a	Transport dheu me auto 5km	m ³	41		
3	3.164/1b	Mbushje me çakell shkembor	m ³	61.5		
4	3.208	Shtrese çakelli t=10cm, makadam, perhapur e ngjeshur me makineri	m ²	348.5		
5	3.212/b	Shtrese stabilizanti ne trotuar T=10cm	m ²	348.5		
6	3.616/a	F V bordura betoni 15x25cm	ml	410		
7	2.262/4	Beton per fiksime bordure C16/20	m ³	12.3		

8	3.620	Trotuar, me 6 cm beton, me pllaka	m ²	345.1		
SHUMA III						
IV PUNIME PER NDRICIMIN						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.654/1	F.V. Tub korrogato Ø80 per telefonine	ml	410		
2	3.654/1	F.V. Tub korrogato Ø80 per elektrikun, ndriçimin	ml	410		
3	3.170	F V pusete elektrike kontrolli PVC 40x40x40cm	cope	7		
4	An-19	F.v puseta betoni me kapak gize 80x80x100mm	cope	2		
5	3.139	Germime dheu me ekskavator me goma	m ³	36.9		
6	3.158/5a	Transport dheu me auto 5km	m ³	36.9		
7	2.261	Mbushje me rere	m ³	24.6		
8	3.353	Mbushje me shkemb te germuar me pare	m ³	12.3		
SHUMA IV						
SHUMA A						
TVSH 20%						
TVSH TOTALE						

Shenim: Preventivi eshte hartuar ne baze te VKM nr.216, date 13.04.2023

Preventivues:

Ing. Eglantina Disha

Drejtori P.I-se
Ing. Flora MUÇA

**MIRATOI
Rakip SULI**

