

**PROJEKT - ZBATIM
PREVENTIVI I PUNIMEVE**

**OBJEKTI: "ASFALTIM I RRUGEVE LIDHESE TE FSHATRAVE NJESITE ADMINSITRATIVE
BURREL, BAZ, LIS, KOMSI, RUKAJ"**

Nr.	Pershkrimi i Objektit	Gjatesia	Shuma
1	Ura e Kale-Frankth	2,683	
2	Ura e Kale - Bater e madhe	1,217	
3	Rruga e Fshatit Midhe	2,150	
4	Ura Bater e vogel-Fshati Pjeze	1,513	
5	Rruga e Fshatit Mallunxe	2,476	
6	Rruga Xhami -Fshati Karice	1,919	
7	Ura Karices-Rrethebaz	3,712	
8	Urake-Bruc	5,079	
9	Shesh Ferre-Rukaj (Shkolla)	2,209	
10	Baz Qender - Kryqezimi Kisha-Koder e keqe	1,305	
11	Rruga Nacionale-Lagjia Kolaj2	1,263	
12	Rruga Nacionale-Lagjia Kolaj1	1,082	
13	Rruga Ndreaj-Rezervuari-Lagjia Re (rruget lidhese)	2,365	
14	Rruga Unaza Qytetit-Ish Reparti-Lagji Dishukaj	789	
15	Rruga Lagjia Ahmetsulaj-Ura Matit (Zenisht)	525	
16	Rruga Fshati shoshaj-Lagjia Nuraj	462	
17	Rruga Lidhese Bater e Vogel (Posum) - Rruga Nacionale	1,445	
18	Sistemim Dhe Rehabilitim i Rugeve Lidhese (Urake-Muzhake-Karice-Burgajet-Lis. Etj)		
	SHUMA TOTALE		
	SHUMA PA TVSH		
	TVSH 20%		
	SHUMA ME TVSH		

PREVENTIVUES

INXHINIER INFRASTRUKTURE
ARBEN IMERI

Digitally signed by Arben
Imeri
Date: 2024.10.21 16:57:41
+02'00'



PROJEKT- ZBATIM
PREVENTIV I PUNIMEVE
"RRUGA UNAZA E QYTETIT-ISH REPARTI-LAGJIA DISHUKAJ"

Nr.	Nr. Anal.	Pershkrimi i Punimeve	Njesia	Sasia	Çmimi (Leke)	Vlera (Leke)
1 - PUNIME PER MBUSHJE DHE GERMIM						
1	3.158/e	Germim e trasport dheu kat I-re me skreper, L=500m dhe V=6~6.5m3	m ³	590.00		
Shuma 1						
2 - PUNIME PER TRUPIN E RRUGES						
1	3.207/1	Shtrese çakelli t=10cm, perhapur e ngjeshur me makineri	m ²	3,156.00		
2	3.212/b	Shtrese stabilizant t=10cm	m ²	3,156.00		
3	3.222/2	Shtrese binderi, me granil gure kave, 6 cm, perhapur e	m ²	2,367.00		
4	3.969/1	Sperkatje me emulsion bituminoz 0.5 l/m2	m ²	2,367.00		
5	3.212/a	Shtrese stabilizanti t=5cm (Per bankina)	m ²	789.00		
6	3.408	F.V. Tuba metalik D=219mm	ml	10.00		
Shuma 2						
3 - PUNIME MURATURE						
1	3.245	Struktura monolite betoni C 25/30	m ³	10.00		
Shuma 3						
Total (1-3)						
Shuma pa TVSH						
Tvsh 20%						
Shuma me TVSH						

PREVENTIVUES
INXHINIER INFRASTRUKTURE
ARBEN IMERI

PROJEKT- ZBATIM
PREVENTIV I PUNIMEVE
"RRUGA NDREAJ-REZERVUARI-LAGJIA RE" (Ruget lidhese)

Nr.	Nr. Anal.	Pershkrimi i Punimeve	Njesia	Sasia	Çmimi (Leke)	Vlera (Leke)
<i>1 - PUNIME PER MBUSHJE DHE GERMIM</i>						
1	3.158/e	Germim e transport dheu kat I-re me skreper, L=500m dhe V=6~6.5m ³	m ³	2,928.00		
					<i>Shuma 1</i>	
<i>2 - PUNIME PER TRUPIN E RRUGES</i>						
1	3.207/1	Shtrese çakelli t=10cm, perhapur e ngjeshur me makineri	m ²	1,642.50		
2	3.212/b	Shtrese stabilizant t=10cm	m ²	1,642.50		
3	3.222/2	Shtrese binderi, me granil gure kave, 6 cm, perhapur e ngjeshur me makineri	m ²	8,277.50		
4	3.969/1	Sperkatje me emulsion bituminoz 0.5 l/m ²	m ²	8,277.50		
5	3.212/a	Shtrese stabilizanti t=5cm (Per bankina)	m ²	2,365.00		
6	3.408	F.V. Tuba metalik D=219mm	ml	10.00		
					<i>Shuma 2</i>	
<i>3 - PUNIME MURATURE</i>						
1	3.245	Struktura monolite betoni C 25/30	m ³	10.00		
					<i>Shuma 3</i>	
					Total (1-3)	
					Shuma pa TVSH	
					Tvsh 20%	
					Shuma me TVSH	

PREVENTIVUES
INXHINIER INFRASTRUKTURE
ARBEN IMERI

**PROJEKT- ZBATIM
PREVENTIV I PUNIMEVE
"RRUGA NACIONALLE - LAGJIA KOLAJ 1"**

Nr.	Nr. Anal.	Pershkrimi i Punimeve	Njesia	Sasia	Çmimi (Leke)	Vlera (Leke)
1 - PUNIME PER MBUSHJE DHE GERMIM						
1	3.158/e	Germim e transport dheu kat I-re me skreper, L=500m dhe V=6~6.5m ³	m ³	1,082.00		
					Shuma 1	
2 - PUNIME PER TRUPIN E RRUGES						
1	3.207/1	Shtrese çakelli t=10cm, perhapur e ngjeshur me makineri	m ²	4,300.00		
2	3.212/b	Shtrese stabilizant t=10cm	m ²	4,300.00		
3	3.222/2	Shtrese binderi, me granil gure kave, 6 cm, perhapur e	m ²	3,225.00		
4	3.969/1	Sperkatje me emulsion bituminoz 0.5 l/m ²	m ²	3,225.00		
5	3.212/a	Shtrese stabilizanti t=5cm (Per bankina)	m ²	1,075.00		
6	3.408	F.V. Tuba metalik D=219mm	ml	10.00		
					Shuma 2	
3 - PUNIME MURATURE						
1	3.245	Struktura monolite betoni C 25/30	m ³	10.00		
					Shuma 3	
					Total (1-3)	
					Shuma pa TVSH	
					Tvsh 20%	
					Shuma me TVSH	

**PREVENTIVUES
INXHINIER INFRASTRUKTURE
ARBEN IMERI**

**PROJEKT- ZBATIM
PREVENTIV I PUNIMEVE
"RRUGA NACIONALLE - LAGJIA KOLAJ 2"**

Nr.	Nr. Anal.	Pershkrimi i Punimeve	Njesia	Sasia	Çmimi (Leke)	Vlera (Leke)
1 - PUNIME PER MBUSHJE DHE GERMIM						
1	3.158/e	Germim e transport dheu kat I-re me skreper, L=500m dhe V=6~6.5m ³	m ³	1,045.00		
					Shuma 1	
2 - PUNIME PER TRUPIN E RRUGES						
1	3.207/1	Shtrese çakelli t=10cm, perhapur e ngjeshur me makineri	m ²	5,052.00		
2	3.212/b	Shtrese stabilizant t=10cm	m ²	5,052.00		
3	3.222/2	Shtrese binderi, me granil gure kave, 6 cm, perhapur e	m ²	3,789.00		
4	3.969/1	Sperkatje me emulsion bituminoz 0.5 l/m ²	m ²	3,789.00		
5	3.212/a	Shtrese stabilizanti t=5cm (Per bankina)	m ²	1,263.00		
6	3.408	F.V. Tuba metalik D=219mm	ml	10.00		
					Shuma 2	
3 - PUNIME MURATURE						
1	3.245	Struktura monolite betoni C 25/30	m ³	10.00		
					Shuma 3	
					Total (1-3)	
					Shuma pa TVSH	
					Tvsh 20%	
					Shuma me TVSH	

**PREVENTIVUES
INXHINIER INFRASTRUKTURE
ARBEN IMERI**

PROJEKT - ZBATIM
PREVENTIVI I PUNIMEVE
"RRUGA BAZ QENDER -KRYQEZIMI KISHA - KODER E KEQE"

Nr.	Nr. Anal.	Pershkrimi i Punimeve	Njesia	Sasia	Çmimi (Leke)	Vlera (Leke)
1 - PUNIME PER MBUSHJE DHE GERMIM						
1	3.158/e	Germim e trasport dheu kat I-re me skreper, L=500m dhe V=6~6.5m ³	m ³	1,100.00		
					Shuma 1	
2 - PUNIME PER TRUPIN E RRUGES						
1	3.207/1	Shtrese çakelli t=10cm, perhapur e ngjeshur me makineri	m ²	5,872.50		
2	3.212/b	Shtrese stabilizant t=10cm	m ²	5,535.00		
3	3.222/2	Shtrese binderi, me granil gure kave, 6 cm, perhapur e	m ²	4,567.50		
4	3.969/1	Sperkatje me emulsion bituminoz 0.5 l/m ²	m ²	4,567.50		
5	3.212/a	Shtrese stabilizanti t=5cm (Per bankina)	m ²	1,305.00		
6	3.408	F.V. Tuba metalik D=219mm	ml	10.00		
					Shuma 2	
3 - PUNIME MURATURE						
1	3.245	Struktura monolite betoni C 25/30	m ³	10.00		
					Shuma 3	
					Total (1-3)	
					Shuma pa TVSH	
					Tvsh 20%	
					Shuma me TVSH	

PREVENTIVUES
INXHINIER INFRASTRUKTURE
ARBEN IMERI

PROJEKT - ZBATIM
PREVENTIVI I PUNIMEVE
"RRUGA SHESH FERRE-RUKAJ (SHKOLLA)"

Nr.	Nr. Anal.	Pershkrimi i Punimeve	Njesia	Sasia	Çmimi (Leke)	Vlera (Leke)
1 - PUNIME PER MBUSHJE DHE GERMIM						
1	3.158/e	Germim e transport dhe kat I-re me skreper, L=500m dhe V=6~6.5m3	m ³	1,899.00		
					Shuma 1	
2 - PUNIME PER TRUPIN E RRUGES						
1	3.207/1	Shtrese çakelli t=10cm, perhapur e ngjeshur me makineri	m ²	9,940.50		
2	3.212/b	Shtrese stabilizant t=10cm	m ²	9,940.50		
3	3.222/2	Shtrese binderi, me granil gure kave, 6 cm, perhapur e ngjeshur me makineri	m ²	7,731.50		
4	3.969/1	Sperkatje me emulsion bituminoz 0.5 l/m2	m ²	7,731.50		
5	3.212/a	Shtrese stabilizanti t=5cm (Per bankina)	m ²	2,209.00		
6	3.408	F.V. Tuba metalik D=219mm	ml	10.00		
					Shuma 2	
3 - PUNIME MURATURE						
1	3.245	Struktura monolite betoni C 25/30	m ³	10.00		
					Shuma 3	
					Total (1-3)	
					Shuma pa TVSH	
					Tvsh 20%	
					Shuma me TVSH	

PREVENTIVUES
INXHINIER INFRASTRUKTURE
ARBEN IMERI

PROJEKT - ZBATIM
PREVENTIVI I PUNIMEVE
"RRUGA URAKE - BRUC"

Nr.	Nr. Anal.	Pershkrimi i Punimeve	Njesia	Sasia	Çmimi (Leke)	Vlera (Leke)
1 - PUNIME PER MBUSHJE DHE GERMIM						
1	3.158/e	Germim e transport dhe kat I-re me skreper, L=500m dhe V=6~6.5m3	m ³	5,390.00		
					Shuma 1	
2 - PUNIME PER TRUPIN E RRUGES						
1	3.207/1	Shtrese çakelli t=10cm, perhapur e ngjeshur me makineri	m ²	22,855.50		
2	3.212/b	Shtrese stabilizant t=10cm	m ²	22,855.50		
3	3.222/2	Shtrese binderi, me granil gure kave, 6 cm, perhapur e ngjeshur me makineri	m ²	17,776.50		
4	3.969/1	Sperkatje me emulsion bituminoz 0.5 l/m2	m ²	17,776.50		
5	3.212/a	Shtrese stabilizanti t=5cm (Per bankina)	m ²	5,079.00		
6	3.408	F.V. Tuba metalik D=219mm	ml	20.00		
					Shuma 2	
3 - PUNIME MURATURE						
1	3.245	Struktura monolite betoni C 25/30	m ³	20.00		
					Shuma 3	
					Total (1-3)	
					Shuma pa TVSH	
					Tvsh 20%	
					Shuma me TVSH	

PREVENTIVUES
INXHINIER INFRASTRUKTURE
ARBEN IMERI

PROJEKT - ZBATIM
PREVENTIVI I PUNIMEVE
"RRUGA URA KARICES-RRETHE BAZ"

Nr.	Nr. Anal.	Pershkrimi i Punimeve	Njesia	Sasia	Çmimi (Leke)	Vlera (Leke)
1 - PUNIME PER MBUSHJE DHE GERMIM						
1	3.158/e	Germim e transport dheu kat I-re me skreper, L=500m dhe V=6~6.5m3	m ³	3,897.00		
					Shuma 1	
2 - PUNIME PER TRUPIN E RRUGES						
1	3.207/1	Shtrese çakelli t=10cm, perhapur e ngjeshur me makineri	m ²	16,704.00		
2	3.212/b	Shtrese stabilizant t=10cm	m ²	16,704.00		
3	3.222/2	Shtrese binderi, me granil gure kave, 6 cm, perhapur e ngjeshur me makineri	m ²	12,992.00		
4	3.969/1	Sperkatje me emulsion bituminoz 0.5 l/m2	m ²	12,992.00		
5	3.212/a	Shtrese stabilizanti t=5cm (Per bankina)	m ²	3,712.00		
6	3.408	F.V. Tuba metalik D=219mm	ml	10.00		
					Shuma 2	
3 - PUNIME MURATURE						
1	3.245	Struktura monolite betoni C 25/30	m ³	10.00		
					Shuma 3	
					Total (1-3)	
					Shuma pa TVSH	
					Tvsh 20%	
					Shuma me TVSH	

PREVENTIVUES
INXHINIER INFRASTRUKTURE
ARBEN IMERI

PROJEKT - ZBATIM
PREVENTIVI I PUNIMEVE
"RRUGA XHAMIA - FSHATI KARICE"

Nr.	Nr. Anal.	Pershkrimi i Punimeve	Njesia	Sasia	Çmimi (Leke)	Vlera (Leke)
1 - PUNIME PER MBUSHJE DHE GERMIM						
1	3.158/e	Germim e transport dheu kat I-re me skreper, L=500m dhe V=6~6.5m3	m ³	1,925.00		
					Shuma 1	
2 - PUNIME PER TRUPIN E RRUGES						
1	3.207/1	Shtrese çakelli t=10cm, perhapur e ngjeshur me makineri	m ²	8,635.00		
2	3.212/b	Shtrese stabilizant t=10cm	m ²	8,635.00		
3	3.222/2	Shtrese binderi, me granil gure kave, 6 cm, perhapur e ngjeshur me makineri	m ²	6,716.00		
4	3.969/1	Sperkatje me emulsion bituminoz 0.5 l/m2	m ²	6,716.00		
5	3.212/a	Shtrese stabilizanti t=5cm (Per bankina)	m ²	1,919.00		
6	3.408	F.V. Tuba metalik D=219mm	ml	10.00		
					Shuma 2	
3 - PUNIME MURATURE						
1	3.245	Struktura monolite betoni C 25/30	m ³	10.00		
					Shuma 3	
					Total (1-3)	
					Shuma pa TVSH	
					Tvsh 20%	
					Shuma me TVSH	

PREVENTIVUES
INXHINIER INFRASTRUKTURE
ARBEN IMERI

**PROJEKT - ZBATIM
PREVENTIVI I PUNIMEVE
"RRUGA E FSHATIT MALLUNXE"**

Nr.	Nr. Anal.	Pershkrimi i Punimeve	Njesia	Sasia	Çmimi (Leke)	Vlera (Leke)
1 - PUNIME PER MBUSHJE DHE GERMIM						
1	3.158/e	Germim e transport dheu kat I-re me skreper, L=500m dhe V=6~6.5m3	m ³	3,939.00		
					Shuma 1	
2 - PUNIME PER TRUPIN E RRUGES						
1	3.207/1	Shtrese çakelli t=10cm, perhapur e ngjeshur me makineri	m ²	11,142.00		
2	3.212/b	Shtrese stabilizant t=10cm	m ²	11,142.00		
3	3.222/2	Shtrese binderi, me granil gure kave, 6 cm, perhapur e ngjeshur me makineri	m ²	8,666.00		
4	3.969/1	Sperkatje me emulsion bituminoz 0.5 l/m2	m ²	8,666.00		
5	3.212/a	Shtrese stabilizanti t=5cm (Per bankina)	m ²	2,476.00		
6	3.408	F.V. Tuba metalik D=219mm	ml	10.00		
					Shuma 2	
3 - PUNIME MURATURE						
1	3.245	Struktura monolite betoni C 25/30	m ³	10.00		
					Shuma 3	
					Total (1-3)	
					Shuma pa TVSH	
					Tvsh 20%	
					Shuma me TVSH	

**PREVENTIVUES
INXHINIER INFRASTRUKTURE
ARBEN IMERI**

PROJEKT - ZBATIM
PREVENTIVI I PUNIMEVE
"RRUGA URA BATER E VOGEL-FSHATI PJEZE"

Nr.	Nr. Anal.	Pershkrimi i Punimeve	Njesia	Sasia	Çmimi (Leke)	Vlera (Leke)
1 - PUNIME PER MBUSHJE DHE GERMIM						
1	3.158/e	Germim e transport dheu kat I-re me skreper, L=500m dhe V=6~6.5m3	m ³	1,213.00		
Shuma 1						
2 - PUNIME PER TRUPIN E RRUGES						
1	3.207/1	Shtrese çakelli t=10cm, perhapur e ngjeshur me makineri	m ²	6,763.50		
2	3.212/b	Shtrese stabilizant t=10cm	m ²	6,763.50		
3	3.222/2	Shtrese binderi, me granil gure kave, 6 cm, perhapur e ngjeshur me makineri	m ²	5,260.50		
4	3.969/1	Sperkatje me emulsion bituminoz 0.5 l/m2	m ²	5,206.50		
5	3.212/a	Shtrese stabilizanti t=5cm (Per bankina)	m ²	1,503.00		
6	3.408	F.V. Tuba metalik D=219mm	ml	10.00		
Shuma 2						
3 - PUNIME MURATURE						
1	3.245	Struktura monolite betoni C 25/30	m ³	10.00		
Shuma 3						
Total (1-3)						
Shuma pa TVSH						
Tvsh 20%						
Shuma me TVSH						

PREVENTIVUES
INXHINIER INFRASTRUKTURE
ARBEN IMERI

**PROJEKT - ZBATIM
PREVENTIVI I PUNIMEVE
"RRUGA E FSHATIT MIDHE"**

Nr.	Nr. Anal.	Pershkrimi i Punimeve	Njesia	Sasia	Çmimi (Leke)	Vlera (Leke)
1 - PUNIME PER MBUSHJE DHE GERMIM						
1	3.158/e	Germim e transport dheu kat I-re me skreper, L=500m dhe V=6~6.5m3	m ³	4,688.00		
Shuma 1						
2 - PUNIME PER TRUPIN E RRUGES						
1	3.207/1	Shtrese çakelli t=10cm, perhapur e ngjeshur me makineri	m ²	9,652.00		
2	3.212/b	Shtrese stabilizant t=10cm	m ²	9,652.00		
3	3.222/2	Shtrese binderi, me granil gure kave, 6 cm, perhapur e ngjeshur me makineri	m ²	7,507.00		
5	3.969/1	Sperkatje me emulsion bituminoz 0.5 l/m2	m ²	7,507.00		
4	3.212/a	Shtrese stabilizanti t=5cm (Per bankina)	m ²	2,145.00		
6	3.408	F.V. Tuba metalik D=219mm	ml	10.00		
Shuma 2						
3 - PUNIME MURATURE						
1	3.245	Struktura monolite betoni C 25/30	m ³	10.00		
Shuma 3						
Total (1-3)						
Shuma pa TVSH						
Tvsh 20%						
Shuma me TVSH						

**PREVENTIVUES
INXHINIER INFRASTRUKTURE
ARBEN IMERI**

PROJEKT - ZBATIM
PREVENTIVI I PUNIMEVE
"RRUGA URA E KALE - BATER E MADHE"

Nr.	Nr. Anal.	Pershkrimi i Punimeve	Njesia	Sasia	Çmimi (Leke)	Vlera (Leke)
1 - PUNIME PER MBUSHJE DHE GERMIM						
1	3.158/e	Germim e transport dheu kat I-re me skreper, L=500m dhe V=6~6.5m3	m ³	1,189.00		
					Shuma 1	
2 - PUNIME PER TRUPIN E RRUGES						
1	3.207/1	Shtrese çakelli t=10cm, perhapur e ngjeshur me makineri	m ²	4,688.00		
2	3.212/b	Shtrese stabilizant t=10cm	m ²	4,868.00		
3	3.222/2	Shtrese binderi, me granil gure kave, 6 cm, perhapur e ngjeshur me makineri	m ²	3,651.00		
4	3.969/1	Sperkatje me emulsion bituminoz 0.5 l/m2	m ²	3,651.00		
5	3.212/a	Shtrese stabilizanti t=5cm (Per bankina)	m ²	1,217.00		
6	3.408	F.V. Tuba metalik D=219mm	ml	10.00		
					Shuma 2	
3 - PUNIME MURATURE						
1	3.245	Struktura monolite betoni C 25/30	m ³	10.00		
					Shuma 3	
					Total (1-3)	
					Shuma pa TVSH	
					Tvsh 20%	
					Shuma me TVSH	

PREVENTIVUES
INXHINIER INFRASTRUKTURE
ARBEN IMERI

PROJEKT - ZBATIM
PREVENTIVI I PUNIMEVE
"RRUGA URA E KALE-FRANKTH"

Nr.	Nr. Anal.	Pershkrimi i Punimeve	Njesia	Sasia	Çmimi (Leke)	Vlera (Leke)
1 - PUNIME PER MBUSHJE DHE GERMIM						
1	3.158/e	Germim e transport dheu kat I-re me skreper, L=500m dhe V=6~6.5m3	m ³	2,806.00		
Shuma 1						
2 - PUNIME PER TRUPIN E RRUGES						
1	3.207/1	Shtrese çakelli t=10cm, perhapur e ngjeshur me makineri	m ²	12,073.00		
2	3.212/b	Shtrese stabilizant t=10cm	m ²	12,073.00		
3	3.222/2	Shtrese binderi, me granil gure kave, 6 cm, perhapur e ngjeshur me makineri	m ²	9,390.00		
4	3.969/1	Sperkatje me emulsion bituminoz 0.5 l/m2	m ²	9,390.00		
5	3.212/a	Shtrese stabilizanti t=5cm (Per bankina)	m ²	2,683.00		
6	3.408	F.V. Tuba metalik D=219mm	ml	10.00		
Shuma 2						
3 - PUNIME MURATURE						
1	3.245	Struktura monolite betoni C 25/30	m ³	10.00		
Shuma 3						
Total (1-3)						
Shuma pa TVSH						
Tvsh 20%						
Shuma me TVSH						

PREVENTIVUES
INXHINIER INFRASTRUKTURE
ARBEN IMERI

PROJEKT - ZBATIM
PREVENTIVI I PUNIMEVE
"RRUGA LAGJIA AHMETSULAJ - URA E MATIT (ZENISHT)"

Nr.	Nr. Anal.	Pershkrimi i Punimeve	Njesia	Sasia	Çmimi (Leke)	Vlera (Leke)
1 - PUNIME PER MBUSHJE DHE GERMIM						
1	3.158/e	Germim e transport dheu kat I-re me skreper, L=500m dhe V=6~6.5m3	m ³	765.00		
Shuma 1						
2 - PUNIME PER TRUPIN E RRUGES						
1	3.207/1	Shtrese çakelli t=10cm, perhapur e ngjeshur me makineri	m ²	210.00		
2	3.212/b	Shtrese stabilizant t=10cm	m ²	2,100.00		
3	3.222/2	Shtrese binderi, me granil gure kave, 6 cm, perhapur e ngjeshur me makineri	m ²	1,575.00		
4	3.969/1	Sperkatje me emulsion bituminoz 0.5 l/m2	m ²	1,575.00		
5	3.212/a	Shtrese stabilizanti t=5cm (Per bankina)	m ²	525.00		
6	3.408	F.V. Tuba metalik D=219mm	ml	10.00		
Shuma 2						
3 - PUNIME MURATURE						
1	3.245	Struktura monolite betoni C 25/30	m ³	10.00		
Shuma 3						
Total (1-3)						
Shuma pa TVSH						
Tvsh 20%						
Shuma me TVSH						

PREVENTIVUES
INXHINIER INFRASTRUKTURE
ARBEN IMERI

PROJEKT - ZBATIM
PREVENTIVI I PUNIMEVE
"RRUGA LIDHESE BATER E VOGEL (POSUM) - RRUGA NACIONALE"

Nr.	Nr. Anal.	Pershkrimi i Punimeve	Njesia	Sasia	Çmimi (Leke)	Vlera (Leke)
1 - PUNIME PER MBUSHJE DHE GERMIM						
1	3.158/e	Germim e transport dheu kat I-re me skreper, L=500m dhe V=6~6.5m3	m ³	1,198.00		
Shuma 1						
2 - PUNIME PER TRUPIN E RRUGES						
1	3.207/1	Shtrese çakelli t=10cm, perhapur e ngjeshur me makineri	m ²	5,780.00		
2	3.212/b	Shtrese stabilizant t=10cm	m ²	5,780.00		
3	3.222/2	Shtrese binderi, me granil gure kave, 6 cm, perhapur e ngjeshur me makineri	m ²	4,335.00		
4	3.969/1	Sperkatje me emulsion bituminoz 0.5 l/m2	m ²	4,335.00		
5	3.212/a	Shtrese stabilizanti t=5cm (Per bankina)	m ²	1,445.00		
6	3.408	F.V. Tuba metalik D=219mm	ml	10.00		
Shuma 2						
3 - PUNIME MURATURE						
1	3.245	Struktura monolite betoni C 25/30	m ³	10.00		
Shuma 3						
Total (1-3)						
Shuma pa TVSH						
Tvsh 20%						
Shuma me TVSH						

PREVENTIVUES
INXHINIER INFRASTRUKTURE
ARBEN IMERI

PROJEKT - ZBATIM
PREVENTIVI I PUNIMEVE
"RRUGA FSHATI SHOSHAJ-LAGJIA NURAJ"

Nr.	Nr. Anal.	Pershkrimi i Punimeve	Njesia	Sasia	Çmimi (Leke)	Vlera (Leke)
1 - PUNIME PER MBUSHJE DHE GERMIM						
1	3.158/e	Germim e transport dheu kat I-re me skreper, L=500m dhe V=6~6.5m3	m ³	733.00		
					Shuma 1	
2 - PUNIME PER TRUPIN E RRUGES						
1	3.207/1	Shtrese çakelli t=10cm, perhapur e ngjeshur me makineri	m ²	1,848.00		
2	3.212/b	Shtrese stabilizant t=10cm	m ²	1,848.00		
3	3.222/2	Shtrese binderi, me granil gure kave, 6 cm, perhapur e ngjeshur me makineri	m ²	1,386.00		
4	3.969/1	Sperkatje me emulsion bituminoz 0.5 l/m2	m ²	1,386.00		
5	3.212/a	Shtrese stabilizanti t=5cm (Per bankina)		462.00		
6	3.408	F.V. Tuba metalik D=219mm	ml	10.00		
					Shuma 2	
3 - PUNIME MURATURE						
1	3.245	Struktura monolite betoni C 25/30	m ³	10.00		
					Shuma 3	
					Total (1-3)	
					Shuma pa TVSH	
					Tvsh 20%	
					Shuma me TVSH	

PREVENTIVUES
INXHINIER INFRASTRUKTURE
ARBEN IMERI

PROJEKT- ZBATIM
PREVENTIV I PUNIMEVE
SISTEMIM DHE REHABILITIM I RRUGEVE LIDHESE (URAKE-MUZHAKË-KARICE -BURGAJET- LIS .ETJ)

Nr	Nr. Anal.	Pershkrimi	Njesia	Sasia	Çmimi	Vlera
2 - PUNIME PER TRUPIN E RRUGES						
1	3.969	Skarifikim shtrese asfalti ekzistues me makineri	m ²	5,100.00		
2	3.969/1	Sperkatje me emulsion bituminoz 0.5l/m2	m ²	5,100.00		
3	3.212/b	Shtrese stabilizant t=10cm	m ²	5,100.00		
4	3.233/2	Shtrese asfaltobetoni me zall lavatrice, 5cm, me makineri	m ²	5,100.00		
					Shuma pa TVSH	
					Tvsh 20%	
					Shuma me TVSH	

PREVENTIVUES
INXHINIER INFRASTRUKTURE
ARBEN IMERI