



BASHKIA HIMARË

PREVENTIVI I PUNIMEVE

OBJEKTI: RIKUALIFIKIM I QENDRËS FSHATI VRANISHT, LOTI 1

Nr	Nr. An	Ferskirim i Punimeve	Njesia	Sasia	Cmimi	Vlera
I PUNIME GERMIMI						
1	3.89/b	Gërmim dheu me eskavator goma 0.25 m ³ , ne kanale gjeresi > 2m, toke zak, kategoria III, me shk ne njet	m ³	1612.0		
2	3.164/1a	Mbushje me material te gërmuar ne trupin e rruges, perhapur e ngjeshur me makineri	m ³	156.0		
3	2.37/5b	Transport materiale ndertimi, dheu me auto deri 10.0 km	m ³	1506.0		
4	2.430/1	Prishje mur guri	m ³	50.0		
SHUMA I						
II PUNIME SHITRESASH						
1	An	Pllake gur, spesori 5 cm	m ²	1882.0		
2	An	Shtrese çakelli t=15 cm, perhapur e ngjeshur me makineri	m ²	1982.0		
3	An	F.V Zgare metalike e elektrosaldaar Ø 6mm/15cm ne te dy drejtimet (Plegma)	m ²	1982.0		
4	2.262/4	Shtrese betoni C 16/20	m ³	198.2		
SHUMA II						
III PUNIME MURE GURI						
1	An	Veshje me gur dekorativ (te shatervani) spesori 2-3 cm	m ²	12.0		
SHUMA III						
IV PUNIME NDRICIMI						
1	3.44/1	Gërmim kanalesh ne toke te bute, me krahe, me seksion deri 0.75 m ² (tubi fleksibel d=50mm dhe bazamenti i shtyllave)	m ³	7.00		
2	3.169	FV shtylla metalike per ndricim, H=5m, d=160mm	copë	8.00		
3	An	FV ndricues Led	copë	8.00		
4	3.168	FV krah shtylla metalike KRH - MS1 1500/1500/10	copë	8.00		
5	3.182	FV elektroda tokezimi te xinguaara 50x3mm L=150cm	copë	8.00		
6	3.176	FV pusete plastike 40x40x40, kapak te forte RIC 1084+1086	copë	8.00		
7	An	F.v Tub fleksibel me dy shtresa d=90mm	ml	170.00		
8	2.261	Shtrese rete (rrethi tubit)	m ³	12.00		
9	An	F.V. Kabell 0,6/1 KV ; tip RG7R ; 5x10mm ²	ml	96.00		
10	4.131/3.5	F.V. Kabell 0,6/1 KV ; tip RG7R ; 4x10mm ²	ml	64.00		
11	An	F.V. Kabell 0,6/1 KV ; tip RG7R ; 3x1,5mm ²	ml	40.00		
12	2.611	Tub pvc Ø 200 (inkastrimin e shvilles)	ml	3.00		
13	2.262/3	Beton C 12/15 (per shtyllat)	m ³	3.00		
14	3.172	F V kuader komardimi komplet me santeri+ fotoelement	copë	1.00		
SHUMA IV						
V PUNIME TE MOBILIMIT URBAN						
1	3.619/a	FV Bordura betoni 6x20 cm	ml	190.0		
2	AN	Tavolina metalike	copë	8.0		
3	AN	Stola metalike	copë	16.0		
4	3.961	F.V. Fidane Peme Dekorative	copë	18.0		
5	3.965	F V shkurre dekorative Juniperus V.18 grup 3 cdo 6.6m	copë	20.0		
6	3.643	Mbjellje bari ne skarpat	m ²	517		
SHUMA V						
VI SINJALISTIKA						
1	3.922	F.v Tabele drejtkëndore (tregimi)(AxB) e zvogeluar 40x60	copë	1.0		
SHUMA VI						
SHUMA (I-VI)						
Fondi rezervë (5%)						
SHUMA PA T.V.SH						
T.V.SH= 20%						
SHUMA TOTALE						

Shënim: per hartimin e preventivit bazuar ne - VKM nr. 216, date 13.04.2023 "Per krijimin dhe funksionimin e sistemit te integruar per informazimin e manualit te çmimeve per zërat e punimeve".

