

Projektuesi: Ing.Aristotel KOCI

Objekti: Rikonstruksion i rruges Dermish

Datë: 14-10-2024

## PREVENTIV

| NR.                         | KODI    | EMËRTIMI I PUNIMEVE   | NJËSIA | SASIA  | ÇMIMI | VLEFTA |
|-----------------------------|---------|---|--------|--------|-------|--------|
|                             |         | <b>1. PUNIME GERMIMI</b>  |        |        |       |        |
| 1                           | 3.122/b | Germim shkemb i coptuar me ekskavator 0.5 m <sup>3</sup> , shkemb, ne themele gjeresi >2 m, me shkarkim ne mjet | m3     | 480.0  |       |        |
|                             |         | <b>Shuma 1:</b>   |        |        |       |        |
|                             |         | <b>2. PUNIME SHITESASH</b>  |        |        |       |        |
| 2                           | 3.211   | Shtrese çakelli mbeturine kave t=20cm, perhapur e ngjeshur me makineri  | m2     | 253.0  |       |        |
| 3                           | 3.212/b | Shtrese stabilizant t=10cm  | m2     | 2430.0 |       |        |
|                             |         | <b>Shuma 2:</b>   |        |        |       |        |
|                             |         | <b>3. NDERTIMI I VEPRAVE TE ARTIT+KANALIZIME</b>  |        |        |       |        |
| 4                           | 3.353   | Mbushje me shkemb te germuar me pare  | m3     | 130.0  |       |        |
|                             |         | <b>Shuma 3:</b>   |        |        |       |        |
|                             |         | <b>4. PUNIME ASFALTIMI</b>  |        |        |       |        |
| 5                           | 3.222/1 | Shtrese benderi me granil gur kave,5cm,me makineri  | m2     | 150.0  |       |        |
|                             |         | <b>Shuma 4:</b>   |        |        |       |        |
|                             |         | <b>5. PUNIME BETONI E BETONARMEJE</b>   |        |        |       |        |
| 6                           | 3.243   | Struktura monolite betoni C 16/20   | m3     | 560.0  |       |        |
|                             |         | <b>Shuma 5:</b>   |        |        |       |        |
|                             |         | <b>6. ANALIZA JASHTE LISTE</b>  |        |        |       |        |
| 7                           | An      | Zgare hekuri Ø4mm me kuadrat 20x20cm (5x2m)   | kg     | 2380.0 |       |        |
|                             |         | <b>Shuma 6:</b>   |        |        |       |        |
| <b>Shuma Analiza</b>        |         |   |        |        |       |        |
| <b>Fondi Rezervë (0.0%)</b> |         |   |        |        |       |        |

|   |  |
|---|--|
| <b>Shuma Analiza + Fondi Rezervë (0.0%)</b> |  |
| <b>TVSH (20%)</b>                           |  |
| <b>Shuma me TVSH</b>                        |  |
| <b>Totali</b>                               |  |

**Preventivuesi:**

Ing.Aristotel KOCI

**Investitori:**

BASHKIA FINIQ

**Shënime:**

Digitally signed by  
Aristotel Koci  
Date: 2024.11.25  
09:25:48 +0200

