



BASHKIA KAMËZ

Seriali: 59D33B24-F5C2-4317-A1C3-9058FE77B219

Projektuesi: BASHKIA KAMËZ

Datë: 20-11-2025

Objekti: SISTEMIM; NDËRTIM KUZ $\Phi 800$ RRUGA XHORXH W. BUSH L=996m
B=5m & KUZ $\Phi 600$ RRUGA BAVARIA L=325m B=4.2m

PREVENTIV PUNIMESH

NR.	KODI	EMËRTIMI I PUNIMEVE.	NJESIA	SASIA	ÇMIMI PA TVSH	VLEFTA PA TVSH
1. ANALIZA TEKNIKE TE REJA 4						
1	4.190	Prerje asfalti me disk, ne te dy anet. Rr. Bavaria	ml	325		
2	4.190	Prerje asfalti me disk, ne te dy anet.	ml	822		
SHUMA 1:						
2. PUNIME SHITESASH						
3	3.969	Skarifikim shtrese asfalti ekzistues me makineri Rr. Bavaria	m2	1040		
4	3.197/ 2	Prishje shtresash ekzistuese, t=10cm. Rr. Bavaria	m2	150		
5	3.164/ 1b	Mbushje me cakell e gur gurore ne trupin e rruges, perhapur e ngjeshur me makineri Rr. Bavaria (kuz)	m3	230		
6	3.164/ 1b	Mbushje me cakell e gur gurore ne trupin e rruges, perhapur e ngjeshur me makineri Rr. Bavaria (shtresa rruge)	m3	49		
7	3.211	Shtrese çakelli mbeturine kave t=20cm, perhapur e ngjeshur me makineri Rr. Bavaria (shtresa rruge)	m2	490		
8	3.212/ b	Shtrese stabilizant t=10cm Rr. Bavaria (shtresa rruge)	m2	490		
9	3.969	Skarifikim shtrese asfalti ekzistues me makineri Rr. Xhorxh Bush	m2	3175		
10	3.164/ 1b	Mbushje me cakell e gur gurore ne trupin e rruges, perhapur e ngjeshur me makineri Rr. Xhorxh Bush Kuz	m3	1200		
11	3.164/ 1b	Mbushje me cakell e gur gurore ne trupin e rruges, perhapur e ngjeshur me makineri Rr. Xhorxh Bush (shtresa rruge)	m3	181		
12	3.211	Shtrese çakelli mbeturine kave t=20cm, perhapur e ngjeshur me makineri Rr. Xhorxh Bush (shtresa rruge)	m2	1810		
13	3.212/ b	Shtrese stabilizant t=10cm Rr. Xhorxh Bush (shtresa rruge)	m2	1810		
SHUMA 2:						
3. PUNIME GERMIMI						
14	3.105/ a	Germim dheu me ekskavator zingjir 0.5 m ³ , ne kanale gjeresi deri 2 m, prani uji ~1m, kategoria IV, me shk ne mjet (Rr. Bavaria)	m3	570		
15	3.158/ 5a	Transport dheu me auto deri 5.0 km (Rr. Bavaria)	m3	570		
16	3.105/ a	Germim dheu me ekskavator zingjir 0.5 m ³ , ne kanale gjeresi deri 2 m, prani uji ~1m, kategoria IV, me shk ne mjet (Rr. Xhorxh Bush)	m3	2600		
17	3.158/ 5a	Transport dheu me auto deri 5.0 km (Rr. Xhorxh Bush)	m3	2600		
SHUMA 3:						
4. TE NDRYSHME, ELEKTRIKE DHE SINJALISTIKA						
18	3.164/ 1t	F.V. Tuba te brinjezuar HDPE SN8 d=315 mm (lidhje)	ml	15		
19	3.164/ 4t	F.V. Tuba te brinjezuar HDPE SN8 d=600 mm (Rr. Bavaria)	ml	319		
20	3.164/ 1t	F.V. Tuba te brinjezuar HDPE SN8 d=315 mm (lidhje)	ml	25		
21	3.164/ 5t	F.V. Tuba te brinjezuar HDPE SN8 d=800 mm (Rr. Xhorxh Bush)	ml	802		
SHUMA 4:						

5. NDERTIMI I VEPRAVE TE ARTIT+KANALIZIME					
22	3.584	Ndertim Pusete kontrolli b/a, 1x1x2 m me kapak gize Rr. Bavaria	copë	6	
SHUMA 5:					
6. ANALIZA TEKNIKE					
23	3.222/2	Shtrese binderi me granil gur kave,6cm,me makineri (Rr. Bavaria)	m2	490	
24	3.226/1	Shtrese asfaltobetoni me granil guri kave, 4cm, me makineri (Rr. Bavaria)	m2	1365	
25	3.222/2	Shtrese binderi me granil gur kave,6cm,me makineri (Rr. Xhorxh Bush)	m2	1810	
26	3.226/1	Shtrese asfaltobetoni me granil guri kave, 4cm, me makineri (Rr. Xhorxh Bush)	m2	4980	
SHUMA 6:					
7. B. SINJALET HORIZONTALE					
27	3.943	Vijezim shirita gjatesor dhe anesor me gjeresi 15 cm. Bikomponente (sprajt) (Rr. Bavaria)	ml	650	
28	3.946	Vijezimet e kalimif te kembesoreve. Bikomponente (sprajt) (Rr. Bavaria)	m2	25	
29	3.943	Vijezim shirita gjatesor dhe anesor me gjeresi 15 cm. Bikomponente (sprajt) (Rr. Xhorxh Bush)	ml	1992	
30	3.946	Vijezimet e kalimit te kembesoreve. Bikomponente (sprajt) (Rr. Xhorxh Bush)	m2	50	
SHUMA 7:					
8. UJESJELLES E KANALIZIM I JASHEM					
31	2.576	Puse kont 1.25x1.25x2.0m Rr. Xhorxh Bush	copë	16	
SHUMA 8:					
Shuma Analiza					
Fondi Rezervë (3.0%)					
Shuma Analiza + Fondi Rezervë (3.0%)					
Shuma TVSH (20%)					
Shuma me TVSH					
Totali					

Preventivuesi: Ing. Denis Prenci



Investitori: BASHKIA KAMËZ

Drejtor i P.I-se: Ing. Ramadan Hysa



**MIRATOI
RAKIP SULI**

KRYETAR

