

Seriali: 06A8E152-A8B7-48DE-AD11-839B5680D167

Projektuesi: B.O.E "HYDRO-ENG CONSULTING" sh.p.k & "ENGINEERING CONSULTING GROUP" sh.p.k & "SIRE-ALB" sh.p.k
Objekti: "Rikonstruksioni i shkalleve Stefanel, Loti II"

Datë: 18-06-2026

PREVENTIV PUNIMESH

NR.	KODI	EMËRTIMI I PUNIMEVE.	NJËSIA	SASIA	ÇMIMI PA TVSH	VLEFTA PA TVSH
		1. PRISHJE				
1	2.426/3	Prishje shtresa betoni	m3	25	0.00	0.00
		SHUMA 1:				0.00
		2. NDERTIMI I VEPRAVE TE ARTIT+KANALIZIME				
2	3.405	Prishje struktura prej guri	m3	13	0.00	0.00
3	3.581	Mbingritje h=0.5 m, Pusete ekzistuese UZ Ø 1.0 m	copë	14	0.00	0.00
		SHUMA 2:				0.00
		3. PUNIME DHEU				
4	2.1a	Germim dheu me krah e transport k dore 10m, kat IV	m3	5	0.00	0.00
5	2.37/2b	Transport materiale ndertimi, dheu me auto deri 7.0 km	m3	48	0.00	0.00
		SHUMA 3:				0.00
		4. PUNIME GERMIMI				
6	3.89/a	Germim dheu me ekskavator goma 0.25 m³, ne kanale gjeresi deri 2 m, toke zak, kategoria III, me shk ne mjet	m3	43	0.00	0.00
		SHUMA 4:				0.00
		5. PUNIME SHITESASH				
7	3.212/b	Shtrese stabilizant t=10cm	m2	385	0.00	0.00
		SHUMA 5:				0.00
		6. PUNIME SHITESASH 2				
8	2.262/4	Shtrese betoni C 16/20	m3	38.5	0.00	0.00
		SHUMA 6:				0.00
		7. PUNIME HEKUR BETONI				
9	2.166	F.V. Hekur betoni periodik Ø 6 - 10 mm	ton	2.22	0.00	0.00
		SHUMA 7:				0.00
		8. ANALIZA JASHTE LISTE				
10	An	Shtirim kalldrem me gurin e zones, permasat e gurit (15xvariabel), trashesia=15 cm	m2	385	0.00	0.00
		SHUMA 8:				0.00
		Shuma Analiza				0.00
		Fondi Rezervë (5.0%)				0.00
		Shuma Analiza + Fondi Rezervë (5.0%)				0.00
		Shuma TVSH (20%)				0.00
		Shuma me TVSH				0.00
		Totali				0.00

Preventivuesi: B.O.E "HYDRO-ENG CONSULTING" sh.p.k & "ENGINEERING CONSULTING GROUP" sh.p.k & "SIRE-ALB" sh.p.k

Investitori: Bashkia Himarë

