

PREVENTIV

OBJEKTI: RIKOSTRUKSION VEPRA UJORE

Nr.	Nr.An.	EMERTIMI I PUNIMEVE	Njesia	Sasia	Çmimi	Vlera
I		SISTEMIM PERROI FSHATI LEMINOT I= 65 ml				
1	3.105/b	Germim dheu me eskavator me gjeresi >2 ,prani uji me shkarkim ne mjet	m3	260		
2	3.158/1a	Transport dheu me auto deri 1 km	m3	260		
3	2.258/2	Nenshtrese zhavori t= 10cm,me ngjeshje	m3	18		
4	3.323	Ndertim mur guri me fugature llç M-50	m3	200		
5	3.243	Beton C - 20/25 (shtresa t=20 cm)	m3	36.5		
6	3.396	Mbushje me cakell pas mureve	m3	90		
8	3.237	Mure butobetoni 25% gure C 16/20(shpatullat e urave)	m3	48		
9	3.244	Struktura monolite betoni C 20/25 (Panelet 460x100x25 cm)	m3	14.5		
10	3.288	F V hekur betoni periodik Ø > 12 mm	ton	1.956		
11	2.262/4	Mbishtrese betoni C16/20 t=5-8 cm	m3	4		
		SHUMA I				
II		SISTEMIM PERROI FSHATI SHQITAS I= 70 ml				
1	3.99/b	Germim dheu me eskavator me gjeresi >2m ,prani uji me shkarkim ne mjet	m3	80		
2	3.158/1a	Transport dheu me auto deri 1 km	m3	80		
3	3.396	Mbushje me cakell pas mureve	m3	35		
4	2.258/2	Nenshtrese zhavori t= 10cm,me ngjeshje	m3	14		
5	3.237	Mure butobetoni 25% gure C12/15 (muret e peroit t= 30cm)	m3	42		
		SHUMA II				
III		NDERTIM PORTBARAZH KANALI KULLUES URA MALIQ				
1	3.99/b	Germim dheu me eskavator me gjeresi >2m ,prani uji me shkarkim ne mjet	m3	20		
2	3.158/1a	Transport dheu me auto deri 1 km	m3	20		
3	2.258/2	Nenshtrese zhavori t= 10cm,me ngjeshje	m3	2		
4	2.262/4	Beton C - 16/20 (shtresa t=30 cm)	m3	6		
5	3.237	Mure butobetoni 25% gure C12/15(muret e prizes)	m3	11		
		SHUMA III				
IV		VEESHJE KANALI UJITES V2 SHQITAS-ZVIRINE L=490 ml				
1	3.102/a	Germim dheu me eskavator me gjeresi deri ne 2m ,prani uji me shkarkim ne toke	m3	135		
2	2.258/2	Nenshtrese zhavori t= 10cm,me ngjeshje	m3	118		
3	2.262/4	Struktura monolite betoni C 16/20 t= 10 cm	m3	103		
		SHUMA IV				
V		VEESHJE KANALI UJITES POTGORIE NR 1 L= 245 ml				
1	3.102/a	Germim dheu me eskavator me gjeresi deri ne 2m ,prani uji me shkarkim ne toke	m3	50		
2	2.258/2	Nenshtrese zhavori t= 10cm,me ngjeshje	m3	59		
3	2.262/4	Struktura monolite betoni C 16/20 t= 10 cm	m3	51.5		
		SHUMA V				
VI		VEESHJE KANALI UJITES POTGORIE NR 2 L= 200 ml				

1	3.102/a	Germim dheu me eskavator me gjeresi deri ne 2m ,prani uji me shkarkim ne toke	m3	40		
2	2.258/2	Nenshtrese zhavori t= 10cm,me ngjeshje	m3	48		
3	2.262/4	Struktura monolite betoni C 16/20 t= 10 cm	m3	42		
		SHUMA VI				
		SHUMA I-VI				
		TVSH 20 %				
		TOTALI				

Preventivi eshte hartuar sipas VKM Nr 216 date 13.04.2023



