

MIRATOHET
 KRYETARI
 FRAN FRROKAJ

PREVENTIV

OBJEKTI: Sistemim I rruges Hydajet Lezha (perballe hotel Leti)

NR.	nr.an.	EMERTIMI I PUNUMEVE	NJESIA	SASIA		
		a, PUNIME GERMIMI				
1	An	Skarifikim shtrese asfalti me makineri	m ²	5,080.0		
		shuma a leke				
		b, PUNIME NE RRUGE				
1	3.227/1	Shtrese binderi me zall lavatrice,3cm,me makineri	m ²	1,120.0		
2	3.231/1	Shtrese asfaltobetoni me zall lavatrice, 4cm, me makineri	m ²	5,080		
		shuma b				
		c, PUNIME NE TROTUARE	m ³	12.0		
1	3.110/b	Germim dheu me eskavator me zinxhire 1.0m ³ , ne kanale me gjeresi >2m, tok zak ,kategoria IV, ,me shkarkim ne mjet (per ndertimin kasonet)	m ³	12.0		
2	3.158/5a	Transport materiale ndertimi, deri 5.0 km	m ²	12.0		
3	3.212/b	Shtrese granili 7cm, me makineri	m ²	500.0		
4	3.620	Trotuar me 6 cm beton, me pllaka	m ³	500.0		
5	3.243/1	Beton C16/20, per kuneta	m ³	35.0		
6	3.617/2	F V bordura betoni 15x35 cm	m	380		
		shuma C leke				
		SHUMA A-C	Leke			
		TVSH 20%	Leke			
		TOTALI	Leke			

Ing. Gjovalin Marku