

**PREVENTIV**

OBJEKTI: NDERTIMI I TROTUARIT NE FSHATIN MANATI

POROSITES: BASHKIA LEZHE

NR.	nr.an.	EMERTIMI I PUNUMEVE	NJESIA	SASIA		
		<b>c, PUNIME NE TROTUARE</b>				
1	3.110/b	Germim dheu me eskavator me zinxhire 1.0m3, ne kanale me gjeresi >2m, tok zak ,kategoria IV, ,me shkarkim ne mjet (per ndertimin kasonet)	m <sup>3</sup>	56.0		
2	2.37/5a	Transport materiale ndertimi, deri 5.0 km	m <sup>3</sup>	56.0		
3	2.258	Mbushje me Nenshtrese zhavori 25cm	m <sup>3</sup>	620.0		
5	ang	Shtrese granili 7cm	m <sup>2</sup>	2,256.0		
6	3.620	trotuar me 6 cm beton, me pllaka	m <sup>2</sup>	2,256.0		
7	2.262/4	Shtrese betoni C16/20, per kuneta	m <sup>3</sup>	105.0		
8	2.262/3	Shtrese betoni C12/15, per bordurat	m <sup>3</sup>	45.0		
9	3.616	F.V. Bordure betoni 12x25 cm	ml	640.0		
10	3.618	F.V. Bordure betoni 20x35 cm	ml	640.0		
		<b>shuma c leke</b>				
		<b>d. PUNIME PER NDRICIMIN RRUGOR+ LINJA REZERVE</b>				
1	4.151/a4 1 4.152/a4 1 4.152/a4 1	F.V.kablo ndricimi Cu i izoluar me gome, pa kutite e derivacionit, vendosje ne mure e soleta, 3x1.5	ml	480.0		
2	4.131/3,5	F.V. ne toke kablo Al fuqie 1000V, i izoluar me gome e mbulesse plasmasi te armuar, 4x 10 mm2	ml	1,200.0		
3	An	F.V. Tub elektrik fleksibel seria e rende Ø 80 mm	ml	720.0		
4	An	F.V. Tub PVC Ø 200 mm per bazamenta shtylle	ml	7.0		
5	An	F.V Shtylle ndricimi metalike H=8 m	cope	41.0		
6	An	F.V Krah per shtylle metalike ndricimi metalike L=1,2m	ml	41.0		
7	An	F.V Ndricues rrugor Led 80W 220v	cope	41.0		
8	An	F.V Morseta per shtylle ndricimi 3P+N 63 A	cope	41.0		
9	2.a-73	Elektroda tokezimi, profil zingato e bakerizuar , L=1.5m	cope	41.0		
10	An	F.V Percjelles Cu 1x10 mm2 per tokezimin	ml	41.0		
11	An	F.V Kapikorda Cu 10x8	cope	62.0		
12	An	F.V Puseta betoni 50x50x50 me kapak betoni	copë	41.0		
13	An	F.V Panel eketrik per komandimin e ndricimit I kompletuar me dy automate, dy kontaktor trefazore 25A dhe sensor muzgu	copë	1.0		
		<b>SHUMA B</b>				
1	3.110/b	Germim dheu me eskavator me zinxhire 1.0m3, ne kanale me gjeresi >2m, tok zak ,kategoria IV, ,me shkarkim ne mjet (per ndertimin kasonet)	m <sup>3</sup>	45.0		
	An-9	Mbushje me zhavorr pas mureve	m3	15.0		
	3.287	F V hekur betoni i zakonshem Ø 6 ~ 10mm	ton	2.4		
	3.244	Struktura monolite betoni C 20/25	m3	40.0		

	3.363	Tombino me tuba betoni Ø 400, mbi shtrese betoni	m	50.0		
		<b>d, PUNIME NE KUB</b>				
1	3.106/b	Germim dheu me eskavator 0.5 m3, ne kanale me gjeresi >2m, tok zak ,kategoria IV, ne prezence uji ~2m,me shkarkim ne mjet	m <sup>3</sup>	12.0		
2	2.258	Nenshtrese zhavori	m <sup>3</sup>	3.0		
4	3.An/2t	F.V. tub PVC Ø400 mm per linjat e jashtme	ml	310.0		
5	An - 22/1	Pusete shiu 40x40,h=100cm, me kapak gize	cope	21		
6	An - 18	Pusete shkarkimi b/a 50x50cm, h=100cm	cope	2		
		<b>shuma c</b>	<b>leke</b>			
		<b>PUNIME GJELBERIMI</b>				
6	ans	FV stola parku	cope	10.0		
		<b>shuma f</b>	<b>Leke</b>			
		<b>SHUMA A-E</b>	<b>Leke</b>			
		<b>TVSH 20%</b>	<b>Leke</b>			
		<b>TOTALI</b>	<b>Leke</b>			<b>-</b>

Ing. Gjovalin Marku

