



DREJTORIA E PERGJITHSHME E PUNEVE PUBLIKE

MIRATOHET

ERION VELIAJ

KRYETAR

Vkt nr. _____ Date _____

PREVENTIV I PUNIMEVE

OBJEKTI: "REHABILITIM I RRUGEVE TE BLOKUT QE KUFIZOHET NGA RRUGET
"LEANDRO ZOTO", "MARIA KRAJA", "DISHA", "SADIK PETRELA"

FAZA: **PROJEKT - ZBATIM**

Nr.	Nr. Anal.	Pershkrimi	Njesia	Sasi	Çmimi (Leke)	Vlera (Leke)
I - PUNIME PER TRUPIN E RRUGES						
1	3.110/b	Germim dheu me ekskavator zinxhir, 1.0 m ³ , ne kanale gjeresi > 2 m, token zak, kategoria IV, me shk ne mjet	m ³	2,001.45		
2	3.352	Mbushje me gur kave	m ³	170.80		
3	An	Frezim asfalti ekzistues (shtresa e tapetit)	m ²	2,510.00		
4	3.211	Shtrese çakelli mbeturine kave t=20cm, perhapur e ngjeshur makineri	m ²	9,685.20		
5	3.212/c	Shtrese stabilizant t=15cm	m ²	15,330.35		
6	3.222/2	Shtrese binderi, me granil gure kave , 6 cm, perhapur e ngjeshur me makineri	m ²	12,427.65		
7	3.226/1	Shtrese asfaltbetoni me granil gure kave , 4 cm, perhapur e ngjeshur me makineri	m ²	14,937.25		
8	3.244	Struktura monolite betoni C 20/25 (per kuneta anesore)	m ³	320.47		
9	2.426/3	Prishje shtresa betoni dhe asfaltbetoni ne trup te rruges	m ³	1,097.25		
10	3.158/5a	Transport dheu me auto deri 5.0 km	m ³	3,070.40		
11	2.426/2	Prishje mur blloqe betoni	m ³	436.05		

12	2.64/2	Mur me tulle plota ne lartesi deri 3m me llaç perzier M 25 (per muret rrethuese)	m ³	107.41		
13	AN	F.V Kangjella dekorative mbi mur + lyerje me dy duar antiruxhio (per muret rrethuese)	m ²	513.70		
14	3.244	F.V Beton M-250 (themeli I murit +brezi) (per muret rrethuese)	m ³	224.16		
15	3.288	F V hekur betoni i zakonshem Ø > 12mm (per muret rrethuese)	kg	60.71		
16	3.An.51	mbushje me zhavorr pas mureve (nen themelet e mureve (per muret rrethuese))	m ³	84.06		
17	3.An/53/H ESK11	Spostim shtylle	cope	24.00		
Shuma I						
II - PUNIME PER TROTUARET						
1	3.98/a	Germim dheu me ekskavator zinxhir 0.25 m ³ , ne kanale gjeresi deri 2 m, toke zak, kategoria III, me shk ne mjet	m ³	1,114.97		
2	2.426/3	Prishje shtresa betoni 10 cm ne zonen e trotuareve	m ³	756.00		
3	3.210	Shtrese çakelli mbeturine kave t=15cm, perhapur e ngjeshur makineri	m ²	7,564.00		
4	3.243	Struktura monolite betoni C 16/20 (per shtrese trotuari)	m ³	756.00		
5	3.618/An2	F V bordura betoni 20x30 cm (C 25/30) (per te gjitha pozicionet e riparimit te tyre)	ml	11,254.00		
6	3.620	Trotuar, me 6 cm beton, me pllaka	m ²	7,564.00		
7	3.620/An3	Heqje pllaka trotuari ekzistuese te demtuara, si dhe per shtrirjen e linjave te reja infrastrukture	m ²	182.00		
8	3.158/5a	Transport dheu me auto deri 5.0 km	m ³	2,113.41		
Shuma II						
III- SINJALISTIKA E SIGURIA						
1	An122	Vijezim shirita gjatesor dhe anesor me gjeresi 12 cm. Bikoponente (sprajt)	ml	13,063.20		
2	An151	Vizime per kembesore dhe shigjeta drejtimi me boje bikoponente	m ²	860.00		
3	An158	FV tabela te ndryshme rrugore D=60cm	cope	127.00		
	An96	Tabela tetekendore e vogel me A-B, 60-20	cope	29.00		
4	An48	Tabele katrore normal me A=60	cope	54.00		
5	An105, man 3	Tabela trekendeshe e vogel a=60 cm	cope	16.00		
Shuma III						

IV- PUNIME NE KANALIZIMET E UJRAVE TE SHIUT						
1	3.98/a	Germim dheu me ekskavator zinxhir 0.25 m ³ , ne kanale gjeresi deri 2 m, toke zak, kategoria III, me shk ne mjet	m ³	3,401.10		
2	3.158/5a	Transport dheu me auto deri 5.0 km	m ³	3,391.92		
3	M.3 An.164/1a	Mbushje me cakell e gur gurore ne trupin e rruges, perhapur e ngjeshur me makineri(trashesia 0.60x0.60 m)	m ³	1,636.08		
4	An – 23/An4	Pusete b/a shiu 40 x 60, h = 100 cm, me kapak kompozit	cope	268.00		
5	3.An/1t	F.V tuba te brinjezuar HDPE SN8 d=315 mm	ml	5,260.00		
Shuma IV						
V. PUNIME NE RRJETIN KUZ						
1	3.98/a	Germim dheu me ekskavator zinxhir 0.25 m ³ , ne kanale gjeresi deri 2 m, toke zak, kategoria III, me shk ne mjet	m ³	1,344.96		
2	3.158/5a	Transport dheu me auto deri 5.0 km	m ³	1,344.96		
3	An.164/1a	Mbushje me cakell e gur gurore ne trupin e rruges, perhapur e ngjeshur me makineri	m ³	672.26		
5	3.An/1t	F.V tuba te brinjezuar HDPE SN8 d=315 mm lidhje me pallatet	ml	1,790.00		
6	An - 20	Pusete shkarkimi b/a, 80 x 80 cm, h = 150 cm	cope	48.00		
7	2575	Puse kontrolli 1x1x1.5m	cope	29.00		
Shuma V						
VI- F.V. HIDRANT DN-80 PN 16						
1	An6	F.V.Stafe e/f plus D-(160x90)mmPE	cope	12.00		
2	119/An7	F.V.Manikote EF Dj-90mm	cope	12.00		
3	98/An8	F.V.Adaptor Dj-90mm	cope	12.00		
4	501/An9	F.V.Fllanxhe Adaptor Dj-90mm	cope	12.00		
5	2.538	F.V.Pje.sp.cel. (brryl δ=7Dj-80mm+mbajtese cel.)	kg	588.00		
6	4.113/2;4/ An10	F.V.Fllanxhe celiku PN16 Dn-80mm	cift	12.00		
7	2.262/3	Shtrese betoni C 12/15	m ³	0.21		

8	An 2.511	Hidrant vertikal Dn 80 PN16	cope	12.00		
9	An/11	Boks metalik	cope	12.00		
Shuma VI						
VII- PUNIME PER NDERTIMIN E NDRIÇIMIT RRUGOR						
1	3.An/53	Shtylla metalike h=7m, d=160mm	cope	246.00		
2	3.An/ksh	F.V. Krah nje degeshe per shtylle metalike per ndricim	cope	246.00		
3	3.An/et	FV elektroda tokezimi te xinguara 50x5x5mm, L=150cm	cope	246.00		
4	An/22	F.V kabell tip FG7(O)R 5x16 mm ² (per kabujt kryesore)	ml	7,150.00		
5	An/21	F.V kabell tip HO7RN-F 3 x 2.5 mm ²	ml	1,722.00		
6	2.a-97	Percjelles tokezimi bakri , Cu, S=50mm ² i zhveshur	ml	369.00		
7	An-22	FV pusete 40x40, h=50cm, me kapak gize	cope	246.00		
8	3.An	F V kuader komandimi komplet me sauter+fotoelement	cope	14.00		
9	AN/hesk	F.V. Tub fleksibel me 2 shtresa D=75mm	ml	5,670.00		
10	An/20	FV morseteri shtylle 3P+sig.8A+kapak	cope	246.00		
11	2.523	F.V. Tub plastik d=200mm (per vendosjen e shtyllave)	ml	295.20		
12	M 3. An-56	F.V. Tuba metalik D=140mm per intersektimet	ml	170.00		
13	2.261	Shtrese rere (nen dhe mbi tubacione + kompaktesim)	m ³	25.00		
14	3.243	Struktura monolite betoni C 16/20 (per fiksimin e shtyllave)	m ³	15.26		
15	3.87/b	Germim dheu per bazamentin e shtyllave dhe pusetat	m ³	29.52		
16	3.158/5a	Transport dheu me auto deri 5.0 km	m ³	29.52		
Shuma VII						
VIII- PUNIME SISTEMIMI & GJELBERIMI						
1	3.25/a	Germim me krah me seksion te deturuar per gropat e pemeve	m ³	33.00		
2	3.619/a	Bordura betoni 6x20x80 cm (per konturimin e fidaneve)	ml	176.00		
3	An164	F.V. Fidane Peme dekorative	cope	30.00		
4	An/14	Sistemim, nivelim dhe pasurim dheu me humus 5kg/m ²	m ²	55.00		

5	An/15	Mbjellje sipërfaqe me bar	m ²	320.00		
6	3.158/5a	Transport dheu me auto deri 5.0 km	m ³	33.00		
7	2.182	Konstruksione metalike 30x15x1.5 mm te thjeshta per pemet 1.05 kg/ml	ton	0.42		
Shuma VIII						
IX- FIBRA OPTIKE DHE SHERBIMET INXHINJERIKE NENTOKESORE						
1	3.98/a	Germim dheu me ekskavator zinxhir 0.25 m ³ , ne kanale gjeresi deri 2 m, toke zak, kategoria III, me shk ne mjet	m ³	1,392.00		
2	An/17	F.V. Tub fleksibel (kurrugat 4 linja) D=90 mm (trotuar)	ml	31,200.00		
3	M.3 An-56	F.V. Tuba metalik D=140mm per intersektimet	ml	145.00		
4	2.261	Shtrese rere (nen dhe mbi tubacione + kompaktesim)	m ³	870.00		
5	An/18	Pusete betoni 1x1x1m me kapak gize	cope	174.00		
6	3.158/5a	Transport dheu me auto deri 5.0 km	m ³	1,392.00		
Shuma IX						
SHUMA TOTALE						
FONDI REZERVE 4%						
SHUMA						
T.V.SH 20 %						
SHUMA ME TVSH						
PAISJE						
1	An/H2	F ndricues Smart, me llampe 80 W (LED me ngjyrë të verdhë)	cope	246.00		
2	An/16	F. Kosha per hedhjen e mbeturinave	cope	95.00		
SHUMA						
VLERA TOTALE						