



BASHKIA HIMARE

Objekti: " NDERTIMI I RRJETIT TE JASHEM TE KANALIZIMEVE TE UJRAVE TE ZEZA DHE STACIONI I POMPIMIT NE POTAM - BASHKIA

EMERTIMI	Njesia	Vlera
SHUMA 1 - RRJETI I KANALIZIMEVE	LEKE	
SHUMA 2 - STACIONI I POMPIMIT 2	LEKE	
SHUMA 3 - STACIONI I POMPIMIT 3	LEKE	
SHUMA 1+2+3	LEKE	
FONDI REZERVE 5 %	LEKE	
SHUMA	LEKE	
TVSH 20%	LEKE	
SHUMA	LEKE	
MAKINERI E PAISJE SHUMA a+b	LEKE	
SHUMA TOTALE	LEKE	

PREVENTIVOI
"DERBI-E"Sh.p.k
Bexhet DEDJA



Objekti: " NDERTIMI I RRJETIT TE JASHEM TE KANALIZIMEVE TE UJRAVE TE ZEZA DHE STACIONI I POMPIMIT NE POTAM - BASHKIA

1- Rrjeti i Kanalizimeve te Ujerve te Zeza

ANALIZA	EMERTIMI	NJESIA	SASIA	CMIMI/NJESI	VLEFTA
I- TUBA TE BRINJEZUAR HDPE					
An	Fv tubo I brinjezuar HDPE Ø 200	ml	235		
An	FV tuba te brinjezuar HDPE SN8 d=250 mm	ml	365.0		
3.An/1t	F V tuba te brinjezuar HDPE SN8 d=315 mm	ml	225.0		
3.An/2t	F V tuba te brinjezuar HDPE SN8 d=400 mm	ml	72.0		
2.523/1	F.V tub plastik d= 200 te brinjezuar per lidhjet e banesave	ml	340.0		
SHUMA I					
II- GERMIME DHE MBUSHJE KANALI					
3.59/c	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi deri 2 m, h=2-3m, toke fort, me shk ne toke	m3	3,090.1		
AN 164/1a	Mbushje me material te germuar ne trupin e rruges, perhapur e ngjeshur me makineri	m3	1,612.0		
2.261	Mbushje tubi me rere	m3	346		
2.37/5a	Transport materiale ndertimi, dheu me auto deri 5.0 km	m3	1,202.98		
SHUMA II					
III-PUSETA BETONI					
An-1	Ndertim puseta betoni H=2-3m, D=1m + kapak gize	cope	33.0		
AN-20	Puse kontrolli 0.8x0.8x1.5m betoni per lidhjet e banesave	cope	26.0		
An-2	Ndertim puseta betoni H=3.5m, D=1.5m + kapak gize	cope	1.0		
SHUMA III					
IV-PUNIME RIPARIM RRUGE					
3.An	Skarifikim shtrese asfalti me makineri	m2	310.00		
2.426/3	Prishje struktura b/a	m3	5		
3.211	Shtrese çakelli mbeturine kave t=20cm, perhapur e ngjeshur makineri	m2	1,630.0		
3.212/c	Shtrese stabilizant t=15cm	m2	1,630.0		
3.229/3	Shtrese binderi me zall lavatrice, 7cm, me makineri	m2	550.0		
3.224/1	Shtrese asfaltobetoni me granil guri kave, 3cm, me makineri	m2	550.0		
SHUMA IV					
SHUMA 1(I+II+III+IV)					

PREVENTIVOI
"DERBI-E"Sh.p.k
Bexhet DEDJA



Objekti: " NDERTIMI I RRJETIT TE JASHEM TE KANALIZIMEVE TE UJRAVE TE ZEZA DHE STACIONI I POMPIMIT NE POTAM - BASHKIA HIMARE "

2.Stacioni i pompimit Nr 2

ANALIZA	EMERTIMI	NJESIA	SASIA	CMIMI/NJESI	VLEFTA
Nr,An	Pershkrimi I punimeve	NJESIA	SASIA	CMIMI	VLEFTA
	I-Dhoma Beton Arme				
2.426/3	Prishje strukture rruge	m3	5		
3.70/b	Germim themel (gropa) sip.10-30 m ² , h= 4.5 m,me makineri.per stacion pompimi	m3	110		
2.258/2	Shtrese zhavorri	m3	12.2		
3.247	Beton C 25/30	m3	8.8		
2.167	Hekur betoni	kg	3100		
2.441	Kallepe per themele	m2	20		
2.448	Kallepe per mure b/a	m2	150		
3.An/fh	Fv watestop tip RT 2000 10*20 &h/izolues tip rapid cement ne bashkimin e kampatave b/a	ml	25		
	shuma 1				
	LINJA E dergimit ND 200 L=180m				
3.An	Skarifikim shtrese asfalti me makineri	m2	220		
2.426/3	Prishje strukture b/a	m3	32		
3.68/2a	Germim kanal shkemb h-2m	m3	250		
2.261	Shtrese rere 10 cm nen tubo	m3	10.5		
2.491/K	F.V Tuba e rakorderi PE d=200mm, t = 14.7 mm, PN 10	ml	180		
2.261	Mbushje me rere mbi tubo	m3	25		
3.378	Mbushje kanali me zhavor	m3	288		
3.211	Shtrese çakelli mbeturine kave t=20cm, perhapur e ngjeshur makineri	m2	260		
3.212/c	Shtrese stabilizant t=15cm	m2	260		
3.224/1	shtrese asfalto betoni	m2	260		
3.229/3	Shtrese binderi 7 cm	m2	260		
2.37/5b	Transport dheu deri 10 km	m3	25		
2.584	Ndertim pusete 1.5*1.5*2m	cope	2		
	SHUMA 2				
	III LINJA NGA PUSETA FUNDORE DERI TE ST.N2 L=40ml				
3.An	Skarifikim shtrese asfalti me makineri	m2	80.00		
2.426/3	Prishje strukture b/a	m3	6		
3.59/c	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi deri 2 m, h=2-3m,token fort,me shk ne toke	m3	80		
2.261	Shtrese rere 10 cm nen tubo	m3	10.5		
3.An/4t	F V tuba te brinjezuar HDPE SN8 d=600 mm	ml	40		
2.261	Mbushje me rere mbi tubo	m3	31		
3.378	Mbushje kanali me zhavor	m3	64		
3.211	Shtrese çakelli mbeturine kave t=20cm, perhapur e ngjeshur makineri	m2	80		
3.212/c	Shtrese stabilizant t=15cm	m2	80		
3.224/1	shtrese asfalto betoni	m2	80		
3.229/3	Shtrese binderi 7 cm	m2	80		
2.37/5b	Transport dheu deri 10 km	m3	12		
2.584	Ndertim pusete 1.5*1.5*2m	cope	1		
	SHUMA 3				
	III Pajisje mekanike				
4.132	Vendosje /montim pompe zhytесе	cope	2		
An	Shufra udhezuese inoksi per cdo pompe	ml	2		



ANALIZA	EMERTIMI	NJESIA	SASIA	CMIMI/NJESI	VLEFTA
An	reduksion inoksi DN 80 ne Dn 150	cope	2		
An	reduksion inoksi DN 200 ne Dn 300	cope	1		
An	Tabo celiku inoksi DN 150	ml	15		
An	Tabo Bye pas Dn 100PN 10	ml	4		
An	Shkalle	cope	1		
An	Fasheta shtrenguese	cope	4		
An	Deflektor inoksi uji	cope	1		
An	Zinxhir per nxjerrjen e pompave	ml	10		
An	Tregues niveli	cope	6		
An	Bryl Inoksi DN 150 90°	cope	2		
An	Permistop pusi	cope	8		
An	Valvul flutur celiku Dn 100 SS PN 10	cope	1		
An	Valvol Celiku DN 150 SS PN 10	cope	3		
4.128/4	Valvul moskthimi celiku DN 150	cope	2		
4.128/5	Valvul moskthimi celiku DN 200	cope	2		
	Kolektor inoksi DN 200 PN 10	Kompleti	1		
	Xhunto anti vibruese Dn 150	cope	3		
4.113/4	Fllanxha SS Tub DN 100 PN 10	cope	2		
4.113/4	Fllanxha SS Tub DN 150 PN 10	cope	10		
4.113/8	Fllanxha SS Tub DN 200 PN 10	cope	2		
AN	Vendosje ventilator aksiale per ambjent geryes	cope	2		
2.491/k	Tub ventilimi HDPE , PE100 RC , Dn 200	ml	10		
2.491/j	Tub ventilimi HDPE , PE100 RC , Dn 160	ml	20		
An	Mbules ventilimi rjete	cope	1		
	Shuma 3				
IV	Pjesa elektrike				
An	Montim Panel elektrik GL 600 15 M	cope	1		
An	Automat / leshues pompe	cope	3		
An	Automat me 40 A 3P	cope	3		
An	Mates energjie kontaktor	cope	1		
An	Montim paneli + kabllot	cope	1		
An	F. v linje e furnizimit me energji nga kabina	leke	1		
An	Puseta elektrike PVC & kapak te forte 0.4*0.4*0.4	cope	2		
An	Automat , leshuesa etj	LS	1		
	Shuma 4				
	Shuma 1+2+3+4				

PREVENTIVOI
"DERBI-E"Sh.p.k
Bexhet DEDJA



**Objekti: " NDERTIMI I RRJETIT TE JASHEM TE KANALIZIMEVE TE UJRAVE TE ZEZA
DHE STACIONI I POMPIMIT NE POTAM - BASHKIA HIMARE "**

2.stacioni i pompimit Nr 3

ANALIZA	EMERTIMI	NJESIA	SASIA	CMIMI/NJESI	VLEFTA
	STACIONI I POMPIMIT Nr 3				
I	Dhoma Beton Arme				
2.426/3	Prishje strukture rruge	m3	5		
3.70/b	Germim themel (gropa) sip.10-30 m ² , h= 4.5 m,me makineri.per stacion pompimi	m3	90		
2.258/2	Shtrese zhavorri	m3	11.5		
3.247	Beton C 25/30	m3	7.5		
2.167	Hekur betoni	kg	2950		
2.441	Kallepe per themele	m2	20		
2.448	Kallepe per mure b/a	m2	150		
3.An /fh	Fv watestop tip RT 2000 10*20 &h/izolues tip rapid cement ne bashkimin e kampatave b/a	ml	25		
	shuma 1				
II	LINJA E dergimit ND 110 ,L=280m				
2.426/3	Prishje strukture rruge	m3	10		
3.59/c	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi deri 2 m, h=2-3m, toke fort, me shk ne toke	m3	392		
2.261	Mbushje tubi me rere	m3	16.8		
2.491/h	F.V Tuba e rakorderi PE d=110mm, t = 8.1 mm, PN 10	ml	280		
2.261	Mbushje me rere mbi tubo	m3	39.2		
AN 164/1	Mbushje me material te germuar ne trupin e rruges, perhapur e ngjeshur me makineri	m3	269		
3.211	Shtrese cakelli mbeturine kave t=20cm, perhapur e ngjeshur makineri	m2	196		
3.212/c	Shtrese stabilizant t=15cm	m2	196		
3.224/1	shtrese asfalto betoni	m2	10		
3.229/3	Shtrese binderi 7 cm	m2	10		
2.37/5b	Transport dheu deri 10 km	m3	25		
2.584	Ndertim pusete 1.5*1.5*2m	cope	1		
	SHUMA 2				
III	Pajisje mekanike				
4.132	Vendosje /montim pompe zhytесе	cope	2		
An	Shufra udhezuese inoksi per cdo pompe	ml	2		
An	reduksion inoksi DN 80 ne Dn 150	cope	2		
An	reduksion inoksi DN 200 ne Dn 300	cope	1		
An	Tubo celiku inoksi DN 150	ml	15		
An	Tubo Bye pas Dn 100PN 10	ml	4		
An	Shkalle	cope	1		
An	Fasheta shtrenguese	cope	4		
An	Deflektor inoksi uji	cope	1		
An	Zinxhir per nxjerrjen e pompave	ml	10		
An	Tregues niveli	cope	6		
An	Bryl Inoksi DN 150 90°	cope	2		
An	Permistop pusi	cope	8		
An	Valvul flutur celiku Dn 100 SS PN 10	cope	1		
An	Valvol Celiku DN 150 SS PN 10	cope	3		
4.128/4	Valvul moskthimi celiku DN 150	cope	2		
4.128/5	Valvul moskthimi celiku DN 200	cope	2		
An	Kolektor inoksi DN 200 PN 10	Kompleti	1		
An	Xhunto anti vibruese Dn 150	cope	3		
4.113/4	Fllanxa SS Tub DN 100 PN 10	cope	4		
4.113/4	Fllanxa SS Tub DN 150 PN 10	cope	2		
4.113/8	Fllanxa SS Tub DN 200 PN 10	cope	10		
AN	Vendosje ventilator aksiale per ambient geryes	cope	2		
2.491/K	Tub ventilimi HDPE , PE100 RC , Dn 200	cope	1		
2.491/j	Tub ventilimi HDPE , PE100 RC , Dn 160	ml	6		
An	Mbules ventilimi rjete	cope	1		
	Shuma 3				



ANALIZA	EMERTIMI	NJESIA	SASIA	CMIMI/NJESI	VLEFTA
IV	Pjesa elektrike				
An 131.2	Montim Panel elektrik GL 600 15 M	cope	1		
An	Automat / leshues pompe	cope	3		
An	Automat me 40 A 3P	cope	3		
An	Mates energjie kontaktor	cope	1		
An	Montim paneli + kabllot	cope	1		
An	F. v linje e furnizimit me energji nga kabina	leke	1		
An	Puseta elektrike PVC & kapak te forte 0.4*0.4*0.4	cope	2		
An	Automat , leshuesa etj	LS	1		
	Shuma 4				
	Shuma 1+2+3+4				

PREVENTIVOI
"DERBI-E"Sh.p.k
Bexhet DEDJA

**Objekti: " NDERTIMI I RRJETIT TE JASHEM TE KANALIZIMEVE TE UJRAVE TE ZEZA DHE STACIONI I POMPIMIT NE POTAM - BASHKIA HIMARE "**

a. MAKINERI PAISJE - Stacioni i Pompimit 2.				
An	Furnizim pompe per KUZ. Te dhenat hidraulike te pompes (Pika e punes-Duty Point): Prurja 22 l/sek, Lartesia 20 m K H2O, Shpejtesia 2929 l/min, Permasa e elikes 210 mm, Aksi I pompes prej celiku inoksi, Dimensionet e pompes: Ana e thithjes PN16, Ana e shkarkimit DN 80/Pn 10, Kalimi i lire 80 mm	cope	3.0	
An	Fv gjenerator Diezel ,	cope	1	
An	Fv inverter Atv 61 22 kw 30HP	cope	1	
An	Fv ventilator aksial	cope	1	
An	Fv Panel elektrik G L 600 15 M	cope	1	
SHUMA a				
b. MAKINERI PAISJE - Stacioni i Pompimit PS 3				
An	Furnizim pompe per KUZ. Te dhenat hidraulike te pompes (Pika e punes-Duty Point): Prurja 6.5 l/sek, Lartesia 20 m K H2O, Shpejtesia 2795 l/min, permasa e elikes 140 mm, Aksi I pompes celiku inoksi, Dimensionet e pompes: Ana e thithjes PN16, Ana e shkarkimit DN 50/Pn 10, Kalimi i lire 45 mm	cope	3.0	
An	Fv gjenerator Diezel ,	cope	1	
An	Fv inverter Atv 61 22 kw 30HP	cope	1	
An	Fv ventilator aksial	cope	1	
An	Fv Panel elektrik G L 600 15 M	cope	1	
SHUMA b				
SHUMA A+B				

PREVENTIVOI
"DERBI-E"Sh.p.k
Bexhet DEDJA