

**PREVENTIV DS 1-2-3 (LOTI 8)**

<b>Nr</b>	<b>Nr.An</b>	<b>Pershkrimi i Punimeve</b>	<b>Njesia</b>	<b>Sasia</b>	<b>Çmimi</b>	<b>Vlera</b>
		<b>A - PUNIME PRISHJE</b>				
1	An	Prishje pllaka ekzistuese, ulje e materialit poshte	m <sup>2</sup>	125.00		
2	2.426/3	Prishje shtresa betoni poshte pllakave	m <sup>3</sup>	71.00		
3	An	Prishje suvatim muri	m <sup>2</sup>	15,000.00		
4	426	Prishje mur tulle pa pastrim	m <sup>3</sup>	2,451.00		
5	3.158/5a	Transport mbeturinash deri 5 km	m <sup>3</sup>	2,800.00		
		<b>B-PUNIME MURATURE</b>				
6	64/2	Mur me tulla te zakonshme ll. M-25	m <sup>3</sup>	2,042.00		
7	70/2	Mur me tulla te lehtesuara ll. M-25 (dopio)	m <sup>3</sup>	406.00		
8	86	Mur tulle 8 vrima t=12 cm ll. M-15	m <sup>3</sup>	500.00		
		<b>C-PUNIME SUVATIMI</b>				
9	300	Suvatim solete	m <sup>2</sup>	715.00		
10	310	Suvatim I brendshem mur tulle llac I perzier	m <sup>2</sup>	12,795.00		
11	334	Suvatim I jashtem I zakonshem mur tulle	m <sup>2</sup>	17,997.00		
12	An	Riparim I plasaritjeve te thella te suvase te lokalizuara me rrjete me fibra xhami alkalorezistente dhe llac I perforcuar me fibra per perforcim te muratures	m <sup>2</sup>	150.00		
13	An	Riparim I plasaritjeve siperfaqesore te suvase me hapje deri ne 5 mm me silixhant me baze rezinash akrilike	m <sup>2</sup>	150.00		
14	An	F.V rrjete me fibra xhami alkalorezistente, per perforcim te muratures(1 cm)	m <sup>2</sup>	17,000.00		
15	2.358/b	Veshje fasade me polisterol jeshil t=5cm + rrjete + suva grafiato	m <sup>2</sup>	4,000.00		
16	2.308/a	Suvatim me grafiato h > 4 m	m <sup>2</sup>	3,000.00		
		<b>C-PUNIME NGRITJE KANTIERI</b>				
17	3.837/a	Rrethim kantieri me rrjete teli	m <sup>2</sup>	1,000.00		
		<b>D-PUNIME BETONI</b>				
18	117/1	Punime betoni C 20/25 kollona B/A monolite, trare, mure B/A, soleta, arkitrare	m <sup>3</sup>	121.00		
19	166	FV. Hekur ndertimi Φ 6-10 mm	ton	3.00		
20	167	FV. Hekur ndertimi Φ >10 mm	ton	6.00		
21	121/1	Brez b/a C 16/20	m <sup>3</sup>	50.00		
		<b>E-PUNIME SHITRESASH</b>				
22	265/a	Shtrese me pllaka qeramike me kolle+llac cemento	m <sup>2</sup>	183.00		
23	326/a	Veshje me pllaka majolike	m <sup>2</sup>	120.00		
24	268/a	Bazamake shkalle mermeri t= 2.5 cm	m <sup>2</sup>	1,100.00		
25	324/a	FV plintusa qeramike	m <sup>2</sup>	300.00		
26	404/1	Lyerje me boje plastike	m <sup>2</sup>	90,000.00		
27	404/2	Lyerje me boje plastike me baze akrilik I jashtem	m <sup>2</sup>	35,868.00		
28	2.431	Skela metalike me tubo fasade > 12 m	m <sup>2</sup>	30,000.00		
		<b>F-PUNIME ELEKTRIKE</b>				
29	480/1	F.V tuba plastmasi Φ 18-21 mm	ml	1,895.00		

30	480/2	F.V tuba plastmasi $\Phi$ 22-26 mm	ml	1,050.00		
31	480/3	F.V tuba plastmasi $\Phi$ 27-31 mm	ml	600.00		
32	480/4	F.V tuba plastmasi $\Phi$ 31-40 mm	ml	300.00		
33	483	Priza brenda murit 10 A	cope	110.00		
34	483	F.V celesa te zakonshem brenda murit	cope	169.00		
35	An	Kuti shperndarese plastike PT6	cope	121.00		
36	An	Kuader me 5 automate + celes elektromagnetik (salvavita)	cope	2.00		
37	An	F.Vpercjelles NO7-K 1x 1.5 mm <sup>2</sup>	ml	600.00		
38	An	F.Vpercjelles NO7 V-K 1x 1.0 mm <sup>2</sup>	ml	600.00		
39	An	F.Vpercjelles NO7 V-K 1x 2.5 mm <sup>2</sup>	ml	350.00		
40	An	F.Vpercjelles NO7 V-K 1x 4.0 mm <sup>2</sup>	ml	400.00		
41	An	F.Vpercjelles NO7 V-K 1x 6.0 mm <sup>2</sup>	ml	500.00		
42	An	F.Vpercjelles NO7 W-K 1x 35 mm <sup>2</sup>	ml	250.00		
43	An	F.Vpercjelles NO7 W-K 1x 10 mm <sup>2</sup>	ml	150.00		
44	An	Kasete elektrike ne hyrje	cope	15.00		
45	487	Kuti plastike celesa dhe priza	cope	10.00		
46	An	Bokse elektrike me 25 kontator ( automat e sahat komplet	cope	2.00		
47	An	Celes elektrik deviat	cope	50.00		
		<b>G-PUNIME HIDRAULIKE</b>				
48	494/3	F.v saracineske bronzi 1"	cope	50.00		
49	516	F.V tub I xinguar 1/2"-1" dhe rakorderi	kg	100.00		
		<b>TOTAL</b>				<b>0</b>