

**PREVENTIV DS 1-2-3 (LOTI 3)**

<b>Nr</b>	<b>Nr.An</b>	<b>Pershkrimi i Punimeve</b>	<b>Njesia</b>	<b>Sasia</b>	<b>Çmimi</b>	<b>Vlera</b>
		<b>A - PUNIME PRISHJE</b>				
1	An	Prishje pllaka ekzistuese, ulje e materialit poshte	m <sup>2</sup>	192.00		
2	2.426/3	Prishje shtresa betoni poshte pllakave	m <sup>3</sup>	15.00		
3	An	Prishje tavani me lese kallami	m <sup>2</sup>	500.00		
4	An	Prishje çatie	m <sup>2</sup>	500.00		
5	An	Prishje suvatim muri	m <sup>2</sup>	36,965.00		
6	426	Prishje mur tulle pa pastrim	m <sup>3</sup>	2,100.00		
7	3.158/5a	Transport mbeturinash deri 5 km	m <sup>3</sup>	2,946.20		
		<b>B-PUNIME MURATURE</b>				
8	64/2	Mur me tulla te zakonshme ll. M-25	m <sup>3</sup>	159.90		
9	70/2	Mur me tulla te lehtesuara ll. M-25 (dopio)	m <sup>3</sup>	1,341.00		
10	86	Mur tulle 8 vrima t=12 cm ll. M-15	m <sup>3</sup>	700.00		
		<b>C-PUNIME SUVATIMI</b>				
11	300	Suvatim solete	m <sup>2</sup>	2,500.00		
12	310	Suvatim I brendshem mur tulle llac I perzier	m <sup>2</sup>	16,055.00		
13	334	Suvatim I jashtem I zakonshem mur tulle	m <sup>2</sup>	23,378.00		
14	An	Riparim I plasaritjeve te thella te suvase te lokalizuara	m <sup>2</sup>	500.00		
15	An	Riparim I plasaritjeve siperfaqesore te suvase me hapje deri ne 5 mm	m <sup>2</sup>	200.00		
16	An	F.V rrjete me fibra xhami alkalorezistente, per perforcim te muratures( 1 cm)	m <sup>2</sup>	30,000.00		
17	2.358/b	Veshje fasade me polisterol jeshil t=5cm + rrjete + suva grafiato	m <sup>2</sup>	5,000.00		
18	2.308/a	Suvatim me grafiato h > 4 m	m <sup>2</sup>	4,000.00		
		<b>C-PUNIME NGRITJE KANTIERI</b>				
19	3.837/a	Rrethim rruge me rrjete teli	m <sup>2</sup>	1,500.00		
		<b>D-PUNIME BETONI</b>				
20	117/1	Punime betoni C 20/25 kollona B/A monolite, trare, mure B/A, soleta, arkitrare	m <sup>3</sup>	103.80		
21	166	FV. Hekur ndertimi Φ 6-10 mm	ton	3.30		
22	167	FV. Hekur ndertimi Φ >10 mm	ton	4.40		
23	121/1	Brez b/a C 16/20	m <sup>3</sup>	216.50		
24	An	Riparimi I plasaritjeve ne elemente betoni	ml	150.00		
		<b>E-PUNIME SHITRESASH</b>				

25	2.262	Shtrese betoni C6/10	m <sup>3</sup>	7.70		
26	265/a	Shtrese me pllaka qeramike me kolle+llac cemento	m <sup>2</sup>	114.00		
27	326/a	Veshje me pllaka majolike	m <sup>2</sup>	500.00		
28	268/a	Bazamake shkalle mermeri t= 2.5 cm	m <sup>2</sup>	30.00		
29	324/a	FV plintusa qeramike	m <sup>2</sup>	143.00		
30	404/1	Lyerje me boje plastike	m <sup>2</sup>	28,605.00		
31	404/2	Lyerje me boje plastike me baze akrilik I jashtem	m <sup>2</sup>	37,954.00		
32	2.431	Skela metalike me tubo fasade> 12 m	m <sup>2</sup>	24,716.00		
		<b>F-PUNIME ELEKTRIKE</b>				
33	480/1	F.V tuba plastmasi Φ 18-21 mm	ml	100.00		
34	480/4	F.V tuba plastmasi Φ 31-40 mm	ml	200.00		
35	483	F.V celesa te zakonshem brenda murit	cope	49.00		
36	An	Kuti shperndarese plastike PT6	cope	5.00		
37	An	Kuader me 5 automate + celes elektromagnetik (salvavita)	cope	3.00		
38	An	F.Vpercjelles NO7-K 1x 1.5 mm <sup>2</sup>	ml	185.00		
39	An	F.Vpercjelles NO7 V-K 1x 1.0 mm <sup>2</sup>	ml	110.00		
40	An	F.Vpercjelles NO7 V-K 1x 2.5 mm <sup>2</sup>	ml	250.00		
41	An	F.Vpercjelles NO7 V-K 1x 4.0 mm <sup>2</sup>	ml	500.00		
42	An	F.Vpercjelles NO7 V-K 1x 6.0 mm <sup>2</sup>	ml	650.00		
43	An	F.Vpercjelles NO7 W-K 1x 35 mm <sup>2</sup>	ml	700.00		
44	An	F.Vpercjelles NO7 W-K 1x 10 mm <sup>2</sup>	ml	900.00		
45	An	Kasete lektrike ne hyrje	cope	50.00		
46	487	Kuti plastike celesa dhe priza	cope	4.00		
47	An	Bokse elektrike me 25 kontator ( automat e sahat komplet	cope	5.00		
48	An	Celes elektrik deviat	cope	50.00		
		<b>G-PUNIME HIDRAULIKE</b>				
49	494/3	F.v saracineske bronzi 1"	cope	23.00		
50	516	F.V tub I xinguar 1/2"-1" dhe rakorderi	kg	313.00		
		<b>K-PUNIME MBULIMI</b>				
51	255	Mbulese catie me tjegulla vendi	m <sup>2</sup>	500.00		
52	297/a	Tavan me kartonxhes	m <sup>2</sup>	500.00		
		<b>TOTAL</b>				